

32-31-11 W

Total Doph. 4354
Comm. 1-22-42 Comp. 2-22-42
Shot or Treated.
Contractor. Crow.Drilling Co.
Issued. 3-21-42

County Barber



CASING.

8" 144'
5 1/2" 4325' cemented.

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

sand shale and shells	75	limo	3404
sand and shale	150	shale and limo	3424
shale and shells	1270	sdv shale	3439
anhydrite and shale	1330	shale and limo	3565
anhydrite and salt	1367	sdv shale	3595
salt	1514	shale and limo	3633
salt and anhyarite	1530	shale & sdv strks	3659
lime and shale	1630	limo	3690
shale	1643	sdv lime	3731
lime	1713	limo	3739
broken limo	1773	shale	3763
lime and shale	1836	lime	3861
shale	1926	broken lime	3912
lime rough	1932	lime	3976
lime	1973	lime chert and shale	4023
shale and limo	2060	limo	4069
lime	2073	shale and limo	4122
shale	2098	sdv lime	4138
broken lime	2124	lime	4156
shale and lime	2222	limo and shale	4186
lime	2248	lime	4235
broken limo	2289	shale and lime	4248
sdv shale	2304	lime	4324
lime	2306	chat (sat.Oil & gas)	4327
broken lime	2336	CABLE TOOLS.	
lime	2361	chat 4325-	4354
shale and lime	2452	some oil and water.	
shale	2473		
limo	2521	Total Depth.	
shale and lime	2676		
shale	2719		
sdv lime	2728		
lime	2748		
lime and shale	2858		
lime	2984		
sdv lime	2993		
lime	3027		
broken limo	3048		
lime	3085		
shale and lime	3123		
lime	3159		
shale sticky	3196		
lime	3231		
limo and shale	3292		
lime	3322		
broken limo and shale	3343		
broken limo	3375		