


32-31-11W

County. Barber.

Total Depth. 4426 P.B. 4380
Comm. 6-13-34 Comp. 9-14-34
Shot or Treated.
Contractor.
Issued. 9-22-34

SEP 22 1934



Elevation. 1550

CASING.

15 1/2" 195' 8 1/2" 4345'

Production. 231 B. 24 hrs.

Figures Indicate Bottom of Formations.

surface	10	shale	3610
red rock	925	sdv shale	3645
shale	1120	cored 3645-63 full recovery.	
red rock	1150	sand and shale no shows	3670
shale	1300	lime	3695
lime and salt	1320	shale and lime	3710
shale	1378	shale	3739
shale and shells	1500	shale and sand	3760
lime	1525	broken lime	3785
lime and shale	1600	lime	3827
shale	1615	shale	3861
broken lime	1726	lime	3984
lime	1835	broken lime	4010
shale	1852	lime	4150
lime	1881	shale	4200
shale	1946	lime	4252
lime	1971	shale	4298
shale	1976	shale and shells	4317
lime	1988	lime	4324
shale	2066	shale	4348
lime	2160	sand	4350
shale	2175	show oil.	
broken lime	2194	Cored 4350-55 No recovery.	
shale	2260	Cored 4358-60 1/2 No recovery.	
lime	2306	Top chat	4355
shale	2314	Reduced hole	4360 1/2
lime	2316	chat	4426 T.D.
shale	2440		
lime	2460	Plugged back 4380 Swabbed 21 PHR.	
shale	2469	Water broke in.	
lime	2590		
shale	2640		
shale and shells	2690	Will recement and test again.	
shale	2692		
lime	2700		
shale	2872		
lime	2925		
shale	2980		
sdv lime	3035		
sbale	3045		
lime	3160		
broken lime	3186	broken lime	3385
sdv lime	3201	shale and shells	3425
shale	3260	shale	3488
lime	3280	lime	3517
shale	3355		
sdv shale	3365		
lime and sand	3373		