

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

☒ Letter requesting confidentiality attached.

☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5050 EXPIRATION DATE 6-30-84

OPERATOR Hummon Corporation API NO. 15-007-21,634

ADDRESS 400 One Main Place COUNTY Barber

Wichita, KS 67202 FIELD _____

** CONTACT PERSON Wilber Berg PROD. FORMATION _____

PHONE 316/263-8521 _____ Indicate if new pay.

PURCHASER _____ LEASE Smith

ADDRESS _____ WELL 1-36 ✓

DRILLING Big-H Drilling, Inc. LOCATION C NW/4 SW/4

CONTRACTOR 400 One Main Place 660' Ft. from west Line and

ADDRESS Wichita, Kansas 67202 1980' Ft. from south Line of (E)
the SW (Qtr.) SEC 36 TWP 31 RGE 11 (W).

PLUGGING Big-H Drilling, Inc. WELL PLAT _____ (Office Use Only)

CONTRACTOR 400 One Main Place

ADDRESS Wichita, Kansas 67202

TOTAL DEPTH 3860 PBD _____

SPUD DATE 7/22/83 DATE COMPLETED 7/29/83

ELEV: GR 1625 DF 1636 KB 1638

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 223 DV Tool Used? _____

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Wilber Berg, being of lawful age, hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.

State Geological Survey
WICHITA BRANCH

RECEIVED
AUG 08 1983
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

36	
RELEASED	
Date: AUG 1 1985	FROM CONFIDENTIAL

KCC _____
KGS ☒
SWD/REP _____
PLG. _____

W11-1E-2E

ACO-1 Well History

Side TWO

OPERATOR Hummon Corporation LEASE NAME Smith SEC 36 TWP 31 RGE 11 (W)

WELL NO 1-36

FILL IN WELL INFORMATION AS REQUIRED;

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
ELECT. LOG TOPS				
_____ Check if no Drill Stem Tests Run.			Ind. Cv.	2649 -1011
_____ Check if samples sent Geological Survey.			Tarkio	2851 -1213
			Elgin	3476 -1838
			Heebner	3641 -2003
			Dgs. Sh	3731 -2099
			Lansing	3830 -2192
			LTD	3860
Cored 3684-3714'				
3684-3686' dense lime				
3686-3694' shale				
3694-3698' dense lime				
3698-3704' limestone w/sl. vuggy pin pt. por., sl. oil stain				
3704-3705' dense lime				
3705-3709' shale				
3709-3711' limestone w/ sl. por., bleeding oil, sl. stain, no odor				
3711-3712' limestone w/ sl. por., no stain				
3712-3713' dense lime				
3713-3714' shale				
DST #1: 3682-3714'				
OP 30/60/30/60	SIP 1118-793			
Weak blow died in 20 min.	FP 23-23/28-23			
Rec. 10' mud	HP 2020/2020			
Red Beds 0 225				
Shale 225 790				
Red Beds & Shale 790 1633				
Shale & Lime 1633 3274				
Lime & Shale 3274 3451				
Shale & Lime 3451 3619				
Lime & Shale 3619 3684				
Shale & Lime 3684 3860				
RTD 3860				
If additional space is needed use Page 2				

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	24#	223	Common	225 sx	2% gel 3%cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

State Geological Survey
WICHITA BRANCH



DRILLERS LOG


#1-36 Smith

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
8-5/8" @ 223'	CONTRACTOR:	Big-H Drilling, Inc.	C NW/4 SW/4
w/ 225 sx. cement	COMMENCED:	July 22, 1983	Section 36-31S-11W
			Barber County, Kansas
D & A	COMPLETED:	July 29, 1983	ELEVATION: 1638 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Beds	0	225	
Shale	225	790	
Red Beds & Shale	790	1633	
Shale & Lime	1633	3274	
Lime & Shale	3274	3451	
Shale & Lime	3451	3619	
Lime & Shale	3619	3684	
Shale & Lime	3684	3860	
RTD		3860	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.


Karen R. Tennis


Subscribed and sworn to before me this 2nd day of August, 1983.

SANDRA L. MENDOZA
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 9/13/86

RECEIVED
STATE CORPORATION COMMISSION

AUG 08 1983

CONSERVATION DIVISION
Wichita, Kansas


Notary Public

AUG 13 1985
State Geological Survey
WICHITA BRANCH