

3-31-12W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- W. C. DOENGES  
Farm- Haas No. 1

SEC. 3 T. 31 R. 12W  
NW NW NE

Total Depth. 4732  
Comm. 3-29-53 Comp. 4-21-53  
Shot or Treated.  
Contractor. Coppinger Drilling Co.  
Issued. 5-23-53

County Barber  
KANSAS



Elevation. 1652 D.F.

CASING:  
8 5/8" 380 cem. w/250 sz.

Production. Dry

Figures Indicate Bottom of Formations.

clay & sand	50
clay, sand & red bed	200
red bed & sholls	375
red bed & shale	382
red bed & sholls	600
shale & sholls	780
shale, shells, & red bed	835
anhyd.	865
shale, shells	1600
lime & shale	1760
lime	1805
lime & shale	2165
lime	2205
lime & shale	2430
lime	2520
lime & shale	3060
sandy lime	3165
lime, shale & sand	3240
shale	3340
shale & lime	3415
sand	3500
lime & shale	3620
shale & sdy lime	3695
shale & sand	3750
lime & shale	3829
lime	4042
lime & shale	4072
lime	4174
lime & shale	4254
chert	4302
chert & lime	4317
chert	4344
chert, lime & shale	4365
shale & lime	4425
shale	4445
shale & lime	4510
shale & chert lime	4526
lime & shale	4602
sand, lime, & shale	4654
shale & lime	4720
lime	4732
Total Depth	

Tops:	
Anhyd.	840
Topoka	3119
Elgin sand	3436
Hobner	3547
Douglas	3575
Lansing	3749
Mississippi lime	4239
Viola	4516
Simpson	4574
Arbuckle	4672