

7-31-12W


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
408 East Main Street, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Gress-Winter "A" No. 1

SEC. 7 T. 31 R. 12W
50' E of 6 NW NE

Total Depth. 3705'
Comm. 6-29-65 Comp. 7-8-65
Shot or Treated.
Contractor. White & Ellis Drlg.
Issued. 4-2-66

County Barber
KANSAS



Elevation. 1701' KB

Production. 3,700,000 CFG

CASING:
7" 253' cem w/100 sx.
2 1/2" 3704' cem w/100 sx.

Figures Indicate Bottom of Formations.

cellar	8
soil & red rock	65
red rock	253
red rock & shale	840
shale	1620
lime	2280
lime & shale	2375
lime	2940
shale & lime	3465
lime	3616
sand	3705 RTD
Total Depth	

TOPS: GEOL.	
Heebner	3583
Toronto	3598
Douglas Shale	3616
Douglas Sand	3635
Base of Sand	3662

7-14-65 Welx perforated 10/3636-42'
and 4/3647-50'.

7-15-65 Acidized w/500 gals. 7½% mud acid.