

25-31-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PURCELL-MULL DRILLING CO., INC.
Farm- Kisling No. 1

SEC. 25 T. 31 R. 12W
SW SW NE

Total Depth. 4308'
Comm. 12-26-54 Comp. 1-10-55
Shot or Treated.
Contractor. Purcell-Mull Drlg. Co., Inc.
Issued. 3-26-55

County Barber
KANSAS



CASING:

8 5/8" 125' cem w/100 sx
5 1/2" 4308' cem w/150 sx

Elevation. 1533' DF

Production. 83 BO

Figures Indicate Bottom of Formations.

Meas. from top of Rotary Bushing.

red rock	125
red bed, shale & shells	525
shale & shells	1125
shale & shells & salt	1550
shale & lime	1705
lime & shale	1955
lime	1975
lime & shale	2125
lime	2230
lime & shale	2355
shale & lime	2535
shale & lime & sand	2740
shale & lime	2842
lime & shale	3225
shale & lime	3322
shale & sand	3390
lime & shale	3607
shale & sand	3641
lime	3818
lime & shale	3897
lime	4225
shale & lime	4246
chat	4260
lime (Miss.)	4308
Total Depth	

Tops: R.B.	
Elgin Sand	3375
Heebner	3506
Douglas Sand	3574
Brown Lime	3686
Lansing	3695
Marmaton	4151
Mississippi	4247