


Company. AURORA GASOLINE CO.
 Farm- Clarke No. 1

30-31-12 W
 SEC. 30 T. 31 R. 12W
 NW NW NE

Total Depth. 4680
 Comm. 6-7-55 Comp. 6-25-55
 Shot or Treated.
 Contractor. S. A. Berwick Drilling Co.
 Issued. 8-13-55

County Barber
 KANSAS



8 5/8 @ CASING: 210' w/ 150 sx cmt.

Elevation. 1618 IB

Production. Dry

Figures indicate Bottom of Formations.

surface soil & sand	40
redrock	210
red bed	575
shale	650
shale & shells	1373
anhydrite	1414
shale & shells	1460
shale & lime	1660
lime	2090
lime & shale	2190
shale	3370
lime & shale	3390
lime	3780
lime & chert	4251
lime	4275
lime & chert	4323
lime	4360
lime & shale	4430
lime	4495
lime & shale	4550
sand & shale	4595
lime	4680
Total Depth	

TOPS:

Anhydrite	1373
Heebner	3534
Toronto	3569
Douglas sand	3607
Base Douglas sand	3648
Lansing	3735
Mississippi	4236
Kinderhook	4351
Viola	4449
Simpson shale	4537
Simpson sand	4542
Arbuckle	4652

Ran Halliburton Guard Log

Halliburton TD 4672

DST #1: 3604-30, open 1 hr. weak; steady
 blow thruout, rec. 190' muddy SW, NSO,
 IFP O#, FFP 90#, BHP 1190#/20 min.