

21-31-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- AYLWARD DRILLING CO.
Farm- Elliott No. 1

SEC. 21 T. 31 R. 12W
NW NW SW

Total Depth. 4326'
Comm. 6-10-58 Comp. 6-23-58
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 8-16-58

County Barber

KANSAS



Elevation. 1613' RB

Production. Dry

CASING:
8 5/8" 215' cem w/140 sx.

Figures Indicate Bottom of Formations.

shale & red rock	210
red bed & shells	575
shale & shells	675
red rock & shale	1000
shale & shells	1260
salt	1420
shale & lime	1635
lime	1835
lime w/some shale	2010
lime	2350
lime & shale	3605
sand	3684
lime & shale	3770
lime	4197
lime & shale	4264
lime	4288
cherty lime	4316
lime	4326
Total Depth	

TOPS: ELECTRIC

Heebner	3553
Base Oread	3583
Douglas Sand	3602
Lansing	3746
Base Kansas City	4198
Mississippi	4258
RTD	4322

DST 4260-4284* op 1 hr, weak blow thruout.
Rec. 60' watery mud. IBHP 565#/20 min,
FBHP 82#/30 min, FP 36# to 50#. *Corrected
to Electric log measurements: Drillers
measurements 4264-4288.