


Computer Inventoried



DIAMOND TESTING

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

CONFIDENTIAL

ORIGINAL

DRILL-STEM TEST TICKET

15-077-22440

Company Robba Expl, INC Lease & Well No. Clark 1-7
Contractor L.D. Drig Charge to Robba Expl, INC
Elevation _____ Formation TARK. Effective Pay _____ Ft. Ticket No. _____
Date 6-4-96 Sec. 7 Twp. 31 S Range 12 W County Barber State KANSAS
Test Approved By [Signature] Diamond Representative ROGER D. FRIEDLY

Formation Test No. 1 Interval Tested from 2800 ft. to 2815 ft. Total Depth 2815 ft.
Packer Depth 2795 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Packer Depth 2800 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 2782 ft. Recorder Number 13386 Cap. 3825 P.S.I.
Bottom Recorder Depth (Outside) 2812 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____ P.S.I.

Mud Type Chem Viscosity 31 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 9.6 Water Loss 40+ cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 55,000 P.P.M. Drill Pipe Length 2769 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out NO Anchor Length 15 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 X 1 1/4 in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: Weak 1/8" Decreasing blow - Died in 3 min
2nd Open: NO Blow

Recovered 5 ft. of Drilling mud some oil specks in Tool
Recovered _____ ft. of _____
Recovered _____ ft. of _____

RELEASED

Recovered _____ ft. of _____
Recovered _____ ft. of _____
Recovered _____ ft. of _____
Remarks: 30' Gas in Pipe
Total

OCT 26 1995

FROM CONFIDENTIAL

Time Set Packer(s) 10:25 A.M. Time Started Off Bottom 11:15 A.M. Maximum Temperature 100
Initial Hydrostatic Pressure (A) 1436 P.S.I.
Initial Flow Period Minutes 10 (B) 58 P.S.I. to (C) 39 P.S.I.
Initial Closed In Period Minutes 15 (D) 49 P.S.I.
Final Flow Period Minutes 10 (E) 39 P.S.I. to (F) 39 P.S.I.
Final Closed In Period Minutes 15 (G) 49 P.S.I.
Final Hydrostatic Pressure (H) 1436 P.S.I.

AUG 30 1996

W61-1E-5



DIAMOND TESTING

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

CONFIDENTIAL

DRILL-STEM TEST TICKET

15-077-22440

ORIGINAL

Company R. E. I. Lease & Well No. Clark 1-7
Contractor L. D. Drig Charge to R. E. I.
Elevation _____ Formation TARK. Effective Pay _____ Ft. Ticket No. _____
Date 6-4-94 Sec. 7 Twp. 31 S Range 12 W County Baird State KANSAS
Test Approved By [Signature] Diamond Representative ROGER D. FRIEDLY

Formation Test No. 2 Interval Tested from 2893 ft. to 2912 ft. Total Depth 2912 ft.

Packer Depth 2888 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.

Packer Depth 2893 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.

Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 2875 ft.

Recorder Number 13386 Cap. 3825 P.S.I.

Bottom Recorder Depth (Outside) 2909 ft.

Recorder Number 13498 Cap. 3925 P.S.I.

Below Straddle Recorder Depth _____ ft.

Recorder Number _____ Cap. _____ P.S.I.

Mud Type Chem Viscosity 31

Drill Collar Length _____ ft. I.D. 2 1/4 in.

Weight 9.3 Water Loss 40+ cc.

Weight Pipe Length _____ ft. I.D. 2 7/8 in.

Chlorides 40,000 P.P.M.

Drill Pipe Length 2862 ft. I.D. 3 1/4 in.

Jars: Make BOWEN Serial Number _____

Test Tool Length 31 ft. Tool Size 3 1/2-IF in.

Did Well Flow? NO Reversed Out NO

Anchor Length 19 ft. Size 4 1/2-FH in.

Main Hole Size 7 7/8 Tool Joint Size 4 1/2 in.

Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: Fair 2" blow inc. to strong-OFF BTM BKT 3 min (NO BB)

2nd Open: Good 6" blow inc. to strong-OFF BTM BKT 2 min (VWBB)

Recovered 45 ft. of SOSMW 23% Gas 2% oil 10% wat. 65% mud

Recovered 62 ft. of SOSMW 10% Gas 2% oil 73% wat. 15% mud

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Remarks: 1400' Gas in pipe

RELEASED

Price Job

Other Charges

Insurance

FROM CONFIDENTIAL

Total

Time Set Packer(s) 10:30 A.M. P.M. Time Started Off Bottom 1:00 A.M. P.M. Maximum Temperature 104

Initial Hydrostatic Pressure (A) 1465 P.S.I.

Initial Flow Period Minutes 30 (B) 68 P.S.I. to (C) 49 P.S.I.

Initial Closed In Period Minutes 30 (D) 772 P.S.I.

Final Flow Period Minutes 45 (E) 88 P.S.I. to (F) 78 P.S.I.

Final Closed In Period Minutes 45 (G) 866 P.S.I.

Final Hydrostatic Pressure (H) 1446 P.S.I.

AUG 30 1994

Diamond Testing shall not be liable for damages of any kind to the property or personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.

**DIAMOND TESTING**

P. O. Box 157

HOISINGTON, KANSAS 67544

(316) 653-7550

DRILL-STEM TEST TICKET

15-077-22440

CONFIDENTIAL**ORIGINAL**

Company R.E. I Lease & Well No. Clark 1-7
Contractor L.D. Drig Charge to R.E. I
Elevation 1656 KB Formation Tapoka Effective Pay _____ Ft. Ticket No. _____
Date 6-6-94 Sec. 7 Twp. 31 S Range 12 W County Baker State KANSAS
Test Approved By _____ Diamond Representative ROGER D. FRIEDLY

Formation Test No. 3 Interval Tested from 2359 ft. to 3412 ft. Total Depth 3451 ft.
Packer Depth 3354 ft. Size 6 3/4 in. Packer Depth 3412 ft. Size 6 3/4 in.
Packer Depth 3359 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set 3412

Top Recorder Depth (Inside) 3341 ft. Recorder Number 13556 Cap. 4425 P.S.I.
Bottom Recorder Depth (Outside) 3405 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth 3448 ft. Recorder Number 13386 Cap. 3875 P.S.I.
Mud Type chem Viscosity 43 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 9.3 Water Loss 11-2 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 7000 P.P.M. Drill Pipe Length 3328 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out YES Anchor Length 33 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: STRONG BLOW OFF BTM BKT 20 SEC GTS 4 MIN (SBB)
2nd Open: STRONG BLOW OFF BTM BKT IMMED- (SBB)

Recovered 15 ft. of grey mud
Recovered 216 ft. of OCMW 30% Gas 20% oil 35% wat. 15% mud
Recovered 434 ft. of OCMW 30% ✓ 20% ✓ 47% ✓ 3% m
Recovered 124 ft. of OCMW 5% oil 95% ✓
Recovered 1426 ft. of salt water
Remarks: 2215' Total Fluid

RELEASED**OCT 26 1995****FROM CONFIDENTIAL**

Time Set Packer(s) 11:35 A.M. Time Started Off Bottom 1:45 P.M. Maximum Temperature 112
Initial Hydrostatic Pressure (A) 1622 P.S.I.
Initial Flow Period Minutes 20 (B) 272 P.S.I. to (C) 438 P.S.I.
Initial Closed In Period Minutes 20 (D) 1387 P.S.I.
Final Flow Period Minutes 45 (E) 555 P.S.I. to (F) 998 P.S.I.
Final Closed In Period Minutes 45 (G) 1407 P.S.I.
Final Hydrostatic Pressure (H) 1593 P.S.I.

AUG 30 1994

**DIAMOND TESTING**

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

DRILL-STEM TEST TICKET**15-077-22440****CONFIDENTIAL
ORIGINAL**

Company REI Lease & Well No. Clarke 1-7
Contractor L. D. Dvlg Charge to REI
Elevation 1656 KB Formation Topokg Effective Pay _____ Ft. Ticket No. _____
Date 6-6-94 Sec. 7 Twp. 31 S Range 12 W County Barber State _____
Test Approved By _____ Diamond Representative Roger D. Friedly

Formation Test No. 4 Interval Tested from 3358 ft. to 3396 ft. Total Depth 3451 ft.
Packer Depth 3353 ft. Size 6 3/4 in. Packer Depth 3396 ft. Size 6 3/4 in.
Packer Depth 3358 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set 3396

Top Recorder Depth (Inside) 3340 ft. Recorder Number 13556 Cap. 4425 P.S.I.
Bottom Recorder Depth (Outside) 3389 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth 3448 ft. Recorder Number 13386 Cap. 3875 P.S.I.

Mud Type Chem Viscosity 43 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 9.3 Water Loss 11.2 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 7,000 P.P.M. Drill Pipe Length 3320 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out Yes Tail Anchor Length 38 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 XH in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.


Blow: 1st Open: STRONG BLOW - OFF BTM BKT 20 Sec - GTS 7min (GSS)
2nd Open: STRONG BLOW - OFF BTM BKT 45 Sec - (SSB)

Recovered <u>248</u> ft. of <u>OCmw</u> <u>30% G</u> <u>15% oil</u> <u>25% W.</u> <u>30% Muri</u>	
Recovered <u>124</u> ft. of <u>SOcmw</u> <u>15% v</u> <u>10% v</u> <u>65% v</u> <u>10% v</u>	
Recovered <u>186</u> ft. of <u>SOcmw</u> <u>10% v</u> <u>5% v</u> <u>82% v</u> <u>3% v</u>	
Recovered <u>186</u> ft. of <u>SOsmw</u> _____ <u>2% v</u> <u>96% v</u> <u>2% v</u>	Price Job
Recovered <u>1056</u> ft. of <u>Salt water</u>	Other Charges
Remarks: <u>1800 Total Fluid</u>	Insurance

RELEASED**OCT 26 1995**

Time Set Packer(s) 6:55 ^{A.M.} P.M. Time Started Off Bottom 8:45 ^{A.M.} P.M. Maximum Temperature 114

Initial Hydrostatic Pressure (A) 1642 P.S.I.
Initial Flow Period Minutes 20 (B) 204 P.S.I. to (C) 409 P.S.I.
Initial Closed In Period Minutes 30 (D) 1387 P.S.I.
Final Flow Period Minutes 30 (E) 506 P.S.I. to (F) 801 P.S.I.
Final Closed In Period Minutes 30 (G) 1387 P.S.I.
Final Hydrostatic Pressure (H) 1593 P.S.I.



DIAMOND TESTING

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

CONFIDENTIAL

DRILL-STEM TEST TICKET

15-077-22440

ORIGINAL

Company R.E.I. Lease & Well No. Clarke 1-7
Contractor L.D. Drilling Charge to R.E.I.
Elevation 1656 KB Formation Douglas Effective Pay _____ Ft. Ticket No. _____
Date 6-29-94 Sec. 7 Twp. 31 S Range 12 W County Barber State KANSAS
Test Approved By _____ Diamond Representative ROGER D. FRIEDLY

Formation Test No. 5 Interval Tested from 3557 ft. to 3607 ft. Total Depth 3607 ft.
Packer Depth 3552 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Packer Depth 3557 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 3539 ft. Recorder Number 13386 Cap. 3875 P.S.I.
Bottom Recorder Depth (Outside) 3604 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____ P.S.I.

Mud Type Chem Viscosity 42 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 8.8 Water Loss 8.8 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 10,000 P.P.M. Drill Pipe Length 3521 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out NO Anchor Length 55 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: weak 1/8" blow inc to strong - OFF BTM 2 min GTS 12 min (NBS)
2nd Open: STRONG BLOW OFF BTM 13 KT IMMED

Recovered 77 ft. of Drilling Mud

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Remarks: _____

RELEASED

OCT 26 1995

FROM CONFIDENTIAL

Price Job

Other Charges

Insurance

Total

Time Set Packer(s) 4:10 P.M. Time Started Off Bottom 6:40 P.M. Maximum Temperature 114

Initial Hydrostatic Pressure (A) 1681 P.S.I.

Initial Flow Period Minutes 30 (B) 107 P.S.I. to (C) 97 P.S.I.

Initial Closed In Period Minutes 30 (D) 156 P.S.I.

Final Flow Period Minutes 45 (E) 107 P.S.I. to (F) 97 P.S.I.

Final Closed In Period Minutes 45 (G) 156 P.S.I.

Final Hydrostatic Pressure (H) 1681 P.S.I.

AUG 30 1994



DIAMOND TESTING

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

DRILL-STEM TEST TICKET

15-077-22440

CONFIDENTIAL
ORIGINAL

Company R.E.I. Lease & Well No. C/Clarke 1-7
Contractor L.D. Drilling Charge to R.E.I.
Elevation 1656 KB Formation Douglas Effective Pay _____ Ft. Ticket No. _____
Date 6-8-94 Sec. 7 Twp. 31 S Range 12 W County Barber State KANSAS
Test Approved By _____ Diamond Representative ROGER D. FRIEDLY

Formation Test No. 6 Interval Tested from 3648 ft. to 3678 ft. Total Depth 3678 ft.
Packer Depth 3643 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Packer Depth 3648 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 3630 ft. Recorder Number 13386 Cap. 3875 P.S.I.
Bottom Recorder Depth (Outside) 3675 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____ P.S.I.
Mud Type Chem Viscosity 56 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 8.7 Water Loss 8.8 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 12,000 P.P.M. Drill Pipe Length 3617 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out NO Anchor Length 30 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 XH in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: STRONG BLOW - OFF BTM BKT 45 SEC - GTS 11 MIN (NBB)
2nd Open: STRONG BLOW - OFF BTM BKT Immer- (W 1" BB)

Recovered 45 ft. of Oil, F.P. 10% G 5% oil 10% wat. 75% mud
Recovered 62 ft. of SOS mud 18% G 2% oil 30% 50%
Recovered 62 ft. of SOS W 2% oil 88% wat. 10% mud

Recovered _____ ft. of _____	Price Job
Recovered _____ ft. of _____	Other Charges
Remarks: _____	Insurance
Total	

Time Set Packer(s) 6:35 A.M. Time Started Off Bottom 8:30 A.M. Maximum Temperature 116°
Initial Hydrostatic Pressure (A) 1672 P.S.I.
Initial Flow Period Minutes 10 (B) 97 P.S.I. to (C) 58 P.S.I.
Initial Closed In Period Minutes 30 (D) 1216 P.S.I.
Final Flow Period Minutes 30 (E) 95 P.S.I. to (F) 88 P.S.I.
Final Closed In Period Minutes 45 (G) 1109 P.S.I.
Final Hydrostatic Pressure (H) 1701 P.S.I.

AUG 30 1994



DIAMOND TESTING

P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

CONFIDENTIAL

DRILL-STEM TEST TICKET

ORIGINAL

15-077-22440

Company R. E. I Lease & Well No. Clarke 1-7
Contractor L. D. Drilling Charge to REI
Elevation 1656 KB Formation Drum Effective Pay _____ Ft. Ticket No. _____
Date 6-9-94 Sec. 7 Twp. 31 S Range 12 W County Baker State KANSAS
Test Approved By _____ Diamond Representative ROGER D. FRIEDLY

Formation Test No. 7 Interval Tested from 3923 ft. to 3934 ft. Total Depth 3934 ft.
Packer Depth 3918 ft. Size _____ in. Packer Depth _____ ft. Size _____ in.
Packer Depth 3923 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 3905 ft. Recorder Number 13386 Cap. 3825 P.S.I.
Bottom Recorder Depth (Outside) 3931 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____ P.S.I.

Mud Type Chem Viscosity 48 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 9.3 Water Loss 11.2 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 14,000 P.P.M. Drill Pipe Length 3892 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number N/A Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out NO Anchor Length 11 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 XH in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.


Blow: 1st Open: STRONG BLOW - OFF BTM BKT 15 sec (FRB)
2nd Open: STRONG BLOW - OFF BTM BKT 1 1/2 min (SRB)

Recovered 25 ft. of muddy water 50% water 50% mud
Recovered 186 ft. of silt water

Recovered _____ ft. of _____
Recovered _____ ft. of _____
Recovered _____ ft. of _____
Remarks: GTS 12 min Final shut IN - No gag.
Price **RELEASED**
Other Charges
Insurance **OCT 26 1995**
FROM CONFIDENTIAL
Total

Time Set Packer(s) 9:30 A.M. P.M. Time Started Off Bottom 11:10 A.M. P.M. Maximum Temperature _____
Initial Hydrostatic Pressure _____ (A) 1917 P.S.I.
Initial Flow Period _____ Minutes 20 (B) 107 P.S.I. to (C) 101 P.S.I.
Initial Closed In Period _____ Minutes 30 (D) 1364 P.S.I.
Final Flow Period _____ Minutes 20 (E) 160 P.S.I. to (F) 164 P.S.I.
Final Closed In Period _____ Minutes 30 (G) 1329 P.S.I.
Final Hydrostatic Pressure _____ (H) 1898 P.S.I.

AUG 30 1994



DIAMOND TESTING
P. O. Box 157
HOISINGTON, KANSAS 67544
(316) 653-7550

CONFIDENTIAL

ORIGINAL

DRILL-STEM TEST TICKET

15-077-22440

Company R.E.I. Lease & Well No. Clarke # 1-7
Contractor L.D. Dalg. Charge to REI
Elevation 1656 KB Formation Mud/Mudstone Effective Pay _____ Ft. Ticket No. _____
Date 6-10-94 Sec. 7 Twp. 31 S Range 12 W County Barber State KANSAS
Test Approved By _____ Diamond Representative ROGER D. FRIEDLY

Formation Test No. 8 Interval Tested from 4100 ft. to 4175 ft. Total Depth 4175 ft.
Packer Depth 4095 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Packer Depth 4100 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.
Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 4108 ft. Recorder Number 13386 Cap. 3825 P.S.I.
Bottom Recorder Depth (Outside) 4172 ft. Recorder Number 13498 Cap. 3925 P.S.I.
Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____ P.S.I.

Mud Type Chem Viscosity 43 Drill Collar Length _____ ft. I.D. 2 1/4 in.
Weight 9.3 Water Loss 15.2 cc. Weight Pipe Length _____ ft. I.D. 2 7/8 in.
Chlorides 12,000 P.P.M. Drill Pipe Length 4069 ft. I.D. 3 1/4 in.
Jars: Make BOWEN Serial Number _____ Test Tool Length 31 ft. Tool Size 3 1/2-IF in.
Did Well Flow? NO Reversed Out NO Anchor Length 75 ft. Size 4 1/2-FH in.
Main Hole Size 7 7/8 Tool Joint Size 4 1/2 in. Surface Choke Size 1 in. Bottom Choke Size 5/8 in.

Blow: 1st Open: STRONG BLOW - OFF BTM BKT 1 MIN (NRB)
2nd Open: STRONG BLOW - OFF BTM BKT IMMEDIATE

Recovered 66 ft. of SOCGM 10% Gas 5% oil 10% water 75% mud

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Remarks: 1740' Gas in pipe **RELEASED** Insurance

OCT 26 1995

Time Set Packer(s) 3:00 P.M. Time Started Off Bottom 5:05 P.M. Temperature 123

Initial Hydrostatic Pressure _____ (A) 2065 P.S.I.

Initial Flow Period _____ Minutes 20 (B) 97 P.S.I. to (C) 88 P.S.I.

Initial Closed In Period _____ Minutes 30 (D) 321 P.S.I.

Final Flow Period _____ Minutes 30 (E) 117 P.S.I. to (F) 97 P.S.I.

Final Closed In Period _____ Minutes 45 (G) 263 P.S.I.

Final Hydrostatic Pressure _____ (H) 2025 P.S.I.

AUG 30 1994

Diamond Testing shall not be liable for damages of any kind to the property or personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.