


10-350 W 83 ✓
 MAP NO. _____ SEC. 12 TWP. 31S RGE. 35W
 STATE Kans COUNTY Stevens LOC. C NE NW
 OPERATOR Socony Mobil Oil Co., Inc. FT. FROM _____ LINE
 WELL NO. 6 FARM NAME George B. Strong Unit FT. FROM _____ LINE
 Cutter ELEV. No GR. 2978 DF 2980 K.B.
 FR. 8/13/62 SPUD 8/12/62 COMP. 10/30/62
 CONT. Garvey Drlg. Co. /GEOL. _____



NAME PRODUCING INTERVAL		COMPLETION RECORD		TREATMENT RECORD	
FROM	TO	PERF. W/HOLES			
Chester	5563-72	18		1000 A & Frac	
State Pot (Gas Lift)					
I. P. OIL/DIST.	F 11 BO	WTR. Tr	GAS 180	M.C.F.P.D.	CHK 25/64 HRS. 24
(Twin to Shallow Gas. Well)					

D & A ()

SIP#	FI TP # 90	FI CP# 420	SIBHP
GOR. 16071-1	GR.	PSTD	TD 5690
SIZE	DEPTH	CASING - CEMENT RECORD	DEPTH
8 5/8" @	644	W/SAX. 100	
4 1/2" @	5681	150	

OPERATOR Socony Mobil Oil Co. WELL NO. 6 George B. Strong ELEV. 2978 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	Unit	DEPTH	SUB SEA
(6000' Oil Tst)			DF Tops & Datums:			
			Lans	4105		-1125
RTD (Chest)	5690	-2710	KC	4376		-1396
			Marm	4770		-1790
Core #1 (Morr)	5312-59'		Chero	4956		-1976
	R 47' w/NSO.		Morr	5298		-2318
Core #2 (Chest)	5525-75'		Chest-			
	R 50' W/SO.		Marker	5496		-2516
Core #3 (Chest)	5575-5626'		LTD	N.A.		
	R 51' Total w/23' Sd					
	w/GSG & No Oil Stn.					

RTD 5690, Log , Ran 4 1/2" @ 5681' w/150 sx, Perf 18/5563-72 (Chest), Swb dry, Nat, 1000 A, Swb ld, Swb dry, Sand frac (15,000 GO x 15,000# sd), Swb ld. Gas lift 7 BLO/24 hrs. Rec all ld, Gas lift = 5 BO + 1 BW/24 hrs thru 1/2" Ck, TP 80#, CP 450#, Ga 218 Mcfgpd, GOR 43600:1. State (Gas Lift) Flo 11.2 BO + Tr Wtr/24 hrs, TP 90#, CP 420# thru 25/64" Ck + Gross Ga Gas 180 Mcfgpd, GOR 16071:1. Net Gas Ga 15 Mcfgpd, GOR 1339:1, from Chest 5563-72, 10/17/62.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2980 KB

Winfield 2640 (+334)

Heebner 4042 (-1062)

Toronto 4064 (-1084)

Lansing 4164 (-1184)

"D" Zone 4614 (-1613)

Marmaton 4768 (-1788)

Morrow 5298 (-2318)

Chester 5496 (-2516)

? Sand 5558 (-2578) 2/15, ϕ flo 11 BO/24 hrs + 180 MCF

Sand 5578 (-2598) 0/23; Core GSG, no oil

Ste. Gen 5634 (-2654)

TD 5690