


WC

902866

State KANSAS Field WC
 Company Hugoton Prod. Co. County Stevens
 Farm PANAMA No. 2-12
 Sec. 12 Twp. 31 Range 38W

Spot CHISEL COR - E.N.E. CHISELContractor MidwesternRemarks 6000' TESTComm. 9/20/56 Comp. 12-5-56Elev. DF GL KB 3138 TD 7617 PB 3100Pay 2843-53, 2865-78, 2889-92, 2906-092922-32, 2954-63 Council GroveI.P. 10,124 MTF Press. RP 382Casing Record: 13 3/8 528/500 7"20" 103/4 5 1/2" 3079/16" 85/8 2755/150

MIR	Sample	Log
SEP 28 2420	Wat 3176 ✓	62782
OCT 3 DST #1 2841-2900 op	Top 3540	Nerr 2954
1 hr. GTS 1" 5" g 560 MCF	Heeb 3964 ✓	Kri 2978
30" g 1,020 MCF 45+1 M g 1/140	TOR 3970	Win 2520
MCF. Rec 105' gas cut mud	Lane 4070	UPT R. 2584
FP 100-145 BHP 450/15	Mamm 4710	L " " 2652
DST #2 2953-72 op 1 hr.	Mor 5308 ✓	G.G. 2782
GTS 4" 5" g 139 MCF 30"	sd 5338 ✓	Wat 3174
g 310 MCF 1 M g 375 MCF	Miss 5646 ✓	Top 3536
Rec 20' g CM FP 25-40 BHP	St Louis 5849 ✓	Heeb 3964
485/20.	Spargen 6002 ✓	Tor 4003
3484		Lans 4080
OCT 10 TTD 5377 plup to		Mamm 4676
DST		ck 4873
OCT 17 DST 5328-77 op 1 hr		Atoka 5152
gd th T.O. Rec 270' gcm		Mor 5312
+1980' gcm. FP 360-1090		U Morsd. 5338
BHP 1515/20 TTD 5850 tan		Miss-chest. 5679 ²
schl to 5850		St Gen 5774
6331		Spargen 6028
OCT 24 7150		OSare 6348
		Kinder- 6599
		Viola - 6639
		Simp. 6852
		Ans 6820
		Weather 91 7680

OCT 31 RTD 7688 run Log

D & A deep PD to App 3100'

NOV 7 From 5 1/2 to 3079
CO pf/20/2895-3000 ~~Testing~~

NOV 14 bail 9g w/ph, A/2000m, A, 2500, g 864 MCF,
+60g swph, 5g/250, pf 45/2959-63, 45/2923-32
15/2906-09, 15/2889-92 5g w, A/2000m + 5000
10m BD 3,450 MCF, A/8000, A/8000 7 1/2%, 20m BD 4,000 MCF
PI @ 2880, pf 45/2865-74, 50/2843-53, A/2000m + 5000
10m BD 8,919 MCF, A/8000 + 8000 7 1/2% ~~pp~~
g 4,308 MCF, A/1000 + 6000 7 1/2% 13m BD 4,608 MCF
~~Testing~~

NOV 21 A/3000 5% 3m BD 8,045 MCF, A/3000 5%
3m BD 8,167 MCF ~~Testing~~

NOV 27 A/3000, 5%, 3m BD 8,305 MCF ~~WOT~~

DEC 5 72/20 16,124 MCF RP 382

AMARILLO TOPS

3140 KB

Winfield 2522 (-640)

Heebner 3982 (-842)

Lansing 4086 (-946)

Morrow 5312 (-2172)

"L" Sd 5338 (-2198) T 14', por 12'?, tst'd 1980' GCXW

Chester 5674 (-2534)

St. Gen 5774 (-2634)

Viola 6639 (-3499)

Arbuckle 6920 (-3780)

Weathered Granite 7600 (-4460)

TD 7606 (-4466)

3140
2782
358