

KANSAS DRILLERS LOG

API No. 15 — 007 — 20,488
County Number

Operator
Texas Oil & Gas Corp.

Address
200 W. Douglas, Suite 300, Wichita, Kansas 67202

Well No. 3 Lease Name Maddix "A"

Footage Location
1980 feet from (N) (S) line 1320 feet from (E) (W) line


Principal Contractor H-30, Inc. Geologist High Plains Consulting Ltd.

Spud Date 7-11-77 Total Depth 2900' P.B.T.D. 2716'

Date Completed 9-10-77 Oil Purchaser N/A

S. 1 T. 31S R. 13 E W
Loc. 1980' FSL & 1320' FEL
County Barber

640 Acres
N



Locate well correctly

Elev.: Gr. 1703'
1708' 1711'
DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	273'	Common	250	2% Gel, 3% CaCl
Production		4 1/2"	10.5#	2760'	"	150	"

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD					
Size	Setting depth	Packer set at	4	Deep Penet.	2660-64'
N/A	N/A	N/A	4	Deep Penet.	2660-64'
			4	Deep Penet.	2660-64'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2,500 gal. acid	2660-64'

INITIAL PRODUCTION

Date of first production N/A	Producing method (flowing, pumping, gas lift, etc.) N/A
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls. Gas N/A MCF Water N/A bbls. Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) N/A	Producing interval (s) N/A

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Texas Oil & Gas Corp.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 3	Lease Name Maddix "A"	Dry Hole	
S <u>1</u> T <u>31S</u> R <u>13</u> ^E _(W)			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Herrington	1876	-165	
Towanda	2003	-292	
Ft. Riley	2066	-355	
Florence	2106	-395	
Wreford	2210	-499	
Cottonwood	2396	-685	
Onaga	2650	-939	
Indian Cave	2656	-945	
Wabaunsee	2706	-995	
Stotler	2844	-1133	
TD	2900	-1189	
PBSD	2716	-1005	
CORE #1, 2650-93', w/results as follows: Rec 43'. Rec 9' shale, 11' sand, 5' sand & siltstone, 4' silty shale, 2' siltstone, 1' silty sand, 11' silty shale. FT #1, 2663': SP=150#; SIP=885#; Rec 8.35 CFG, 4500 cc wtr FT #2, 2698': SP=70#; SIP=903#; Rec 6750 cc wtr FT #3, 2682': SIP=909# FT #4, 2675': SP=400#; SIP=906#; Rec 2,000 cc wtr			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	HAROLD A. BROWN Signature District Geologist Title January 25, 1978 Date		

Geological Survey
WICHITA, BRANCH

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

API# 15-007-20,488

15-007-20488

COMPANY Texas Oil & Gas Corp.

FARM Maddix "A"

NO. 3

SEC. 1 T. 31S R. 13W
LOC. 1980' FSL and
1320' FEL

TOTAL DEPTH 2,900'

COMM. July 11, 1977

SHOT OR TREATED


CONTRACTOR H-30, Inc.

ISSUED July 25, 1977

COMP. July 16, 1977

COUNTY Barber

KANSAS



CASING

20
15
12
13

10
8
6
5

5/8" 273' cemented with 250 sxs cement

ELEVATION 1711KB

4 1/2" 2760' cemented with 150 sxs cement

PRODUCTION

Shale
Shale and Lime
Lime and Shale
Shale and Lime
Rotary Total Depth

890'
2,466'
2,693'
2,900'
2,900'

I hereby certify the above and foregoing to be
a true and correct log of the above described well
as shown by the drilling reports.

H-30, Inc.


Dean Britting
Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 25th day of July,



Elsie Willison
Elsie Willison-Notary Public