

7-31-13W


PRYOR AND LOCKHART.
Gant "A" No. 1

SEC. 7 T. 31 R. 13W.
Center SE $\frac{1}{4}$

DEEPENING RECORD - *plotted per*

Total Depth. 4656
Comm. 5-15-37 Comp. 6-11-37
Shot or Treated. 2500 Gal acid.
Contractor. Patton Drlg. Co.
Issued. 4-18-42

County Barbor.



CASING

12 $\frac{1}{2}$ " 607' 7" 4428'
5 $\frac{1}{2}$ " 4550 UR 4574

Elevation.

Production Pot. 1351 B.

Figures Indicate Bottom of Formations.

sdv lime	60
red rock gyp and shells	380
red rock and shale	605
lime	620
shale	650
anhydrite and shale	720
shale and shells	920
red rock and shale	1220
shale and red rock	1485
shale	1520
lime grey broken	1535
shale and shells	1625
shale	1700
lime	2000
broken lime	2300
lime	2460
lime and shale	2540
lime	2855
lime and shale	2925
lime	3385
lime and shale	3570
shale and sand	3620
shale	3640
lime	3650
shale	3675
lime	3695
shale	3745
shale and broken lime	3765
shale	3780
lime	3830
lime and shale	3890
lime	4392
shale	4434
lime	4440
4440 equals 4438 corrected.	
SIM 4438	
Total Depth.	

DEEPENING RECORD.

Comm. 12-20-41 Comp. 2-21-42
Prod. Est. 2 to 3 million gas

5 $\frac{1}{2}$ " 4550 reamed to 4574
lime 4499
lime & chert 4506
lime 4548
shale green 4551
sand and shale 4555
sand 4556
sdv shale 4559
shale green 4560
shale 4573
sand 4574
shale green 4578
sdv shale 4583 1st oil
sand water 4586
water increase 4591 to 96
1000' more water.
sand 4605
4605 equals 15 Corr.
shale 4620
bailing and swabbing hole to
bottom 30 Min test 100' wtr.
sdv shale 4639 Rotary
4639 equals 44 SLC
lime 4656
Total Depth.

Tops	Simpson	4547
	Arb.	4642