

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


7-31-13W

PRYOR & LOCKHART, INC.
Gant "A" No. 2.

SEC. 7 T. 31 R. 13 W
SWc SE

Total Depth. 4569'
Comm. 10-30-42 Comp. 2-2-43
Shot or Treated.
Contractor.
Issued. 4-3-43

County. Barber



CASING:
13 3/8" 231'
7" 4557'

Elevation.

Production. Pot. 201 B.

Figures Indicate Bottom of Formations.

cellar	8	lime & shale	3445	Swabbing
gyp & red rock	82	lime brkn	3465	12-10-42 17 gal.wtr, 14 gal.oil
red rock, gyp,		lime sft	3510	12-14-42 1 gal.oil, 30 gal.wtr
shells	265	lime	3533	12-15-42 shot 40 Qts. 4559-68
red rock	585	lime brkn & shale	3602	12-19-42 swb 28 BW, 10 1/2 BO
anhydrite lime	598	lime & shale	3709	12-24-42 swb 14 4/5 BW, 6 1/3 BO
shale	668	shale	3730	12-26-42 Lane Wells plug 4544-48
anhydrite	730	lime	3746	twelve shots
red rock	820	lime & shale	3765	hole filled 800' w/wtr, no oil
shale	875	sand	3785	making 1 BPH, very little gas
red rock	950	lime brkn	3800	12-30-42 33 shots 4408-12
shale & shells	1265	lime	3922	inc. in gas
salt & shale	1425	lime sft	3948	12-31-42 24 shots 3762 1/2 - 63 1/2
shale & shells	1600	lime	3953	5 BWPH, sh oil
shale	1670	lime sft	3975	32 shots 3760-82
lime	1695	lime	3992	swb 17 BW, rainbow of
lime brkn	1745	lime brkn	4005	oil
lime	1755	lime	4020	1-23-43 750 Gals. Acid
shale	1763	lime sdy	4030	swb 113 BW, oil & gas in 5 1/2 hrs
lime	1800	lime	4074	
shale	1815	lime cherty	4136	
lime	1825	lime & shale	4180	
lime, dolomite,		lime	4200	
shale brks	1928	shale & lime	4220	
lime	1990	shale	4232	
brkn lime & shale	2040	lime	4249	
lime	2118	lime & shale	4268	
shale	2125	lime	4290	
lime	2150	lime cherty	4330	
lime brkn	2168	lime & shale	4401	
lime	2240	cored	4418 1/2	
shale	2275	lime brkn	4442	
lime brkn	2315	lime cherty	4490	
lime	2460	lime	4528	
lime brkn & shale	2542	shale	4547	
lime & shale	2605	cored	4569	
lime	2700			
shale	2712	Rotary Total Depth		
sand	2725	Cable		
shale	2735	Total Depth in sand 4569		
lime	2780			
shale & shells	2815			
lime & shale	2865	Tops:		
lime brkn	2880	Ft. Riley	2068	
shale	2905	Douglas (tested	3764-84	
lime	2932	K. C. (M.G.)	3809	
shale	2950	Mississippi	4307	
lime	3008	Kinderhook	4365	
lime brkn	3012	Misener	4410 1/2	
lime	3026	Viola	4411	
lime & shale	3093	Simpson	4528	
lime brkn & shale	3140	Simpson sand	4557	
lime brkn	3164	Total depth 4569 in sand		
lime	3184			
lime brkn	3224	strong smell of oil &		
lime	3275	gas in samples 3800-05		
lime sft	3293	smell oil & gas in		
lime	3300	sample 3960-65		
shale	3310			
lime shells	3377			
lime brkn	3394			