

7-31-13W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PRYOR & LOCKHART, INC.

SEC. 7 T. 31 R. 13W

FARM Gant "A"

NO. 2


LOC. SW SW SE

DEEPENING RECORD

COUNTY Barber

TOTAL DEPTH 4761
COMM. 10-30-42
SHOT OR TREATED
CONTRACTOR
ISSUED 3-10-51

COMP. 2-2-43



ELEVATION 1688

PRODUCTION 201 bbl. Pot.

CASING

13 3/8" 231'
7" 4557'

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	8	lime brkn	3224	Misener	4410 1/2
gyp & red rock	82	lime	3275	Viola	4411
red rock, gyp, shells	265	lime sft	3293	Simpson	4528
red rock	585	lime	3300	Simpson Sand	4557
anhydrite lime	598	shale	3310		
shale	668	lime shells	3377	Total depth 4569 in sand.	
anhydrite	730	lime brkn	3394	Strong smell of oil & gas in samples 3800-05	
red rock	820	lime & shale	3445	Smell oil & gas in sample 3960-3965	
shale	875	lime brkn	3465	Swabbing	
red rock	950	lime sft	3510	12-10-42 17 gal. wtr, 14 gal. oil	
shale & shells	1265	lime	3533	12-14-42 1 gal. oil, 30 gal. wtr.	
salt & shale	1425	lime brkn & shale	3602	12-15-42 Shot 40 Qts. 4559-68	
shale & shells	1600	lime & shale	3709	12-19-42 Swb 28 BW, 10 1/2 BO	
shale	1670	shale	3730	12-24-42 Swb 14 4/5 BW, 6 1/3 BO	
lime	1695	lime	3746	12-26-42 Lane Wells plug 4544-48	
lime brkn	1745	lime & shale	3765	twelve shots.	
lime	1755	sand	3785	Hole filled 800' w/wtr	
shale	1763	lime brkn	3800	no oil. Making 1 BPH, very little gas.	
lime	1800	lime	3922	12-30-42 33 Shots 4408-12	
shale	1815	lime sft	3948	Inc. in gas.	
lime	1825	lime	3953	12-31-42 24 shots 3762 1/2 - 63 1/2	
lime, dolo., shale brks	1928	lime sft	3975	5 BWP, sh oil	
lime	1990	lime	3992	22 Shots 3760-82	
lime brkn, & shale	2040	lime brkn	4005	Swb 17 BW, rainbow of oil.	
lime	2118	lime	4020	1-23-43 750 Gals acid. Swb 113	
shale	2125	lime sdy	4030	BW, oil & gas in 5 1/2 hrs.	
lime	2150	lime	4074		
lime brkn	2168	lime cherty	4136		
lime	2240	lime & shale	4180		
shale	2275	lime	4200		
lime brkn	2315	shale & lime	4220		
lime	2460	shale	4232		
lime brkn & shale	2542	lime	4249		
lime & shale	2605	lime & shale	4268		
lime	2700	lime	4290		
shale	2712	lime cherty	4330		
sand	2725	lime & shale	4401		
shale	2735	cored	4418 1/2		
lime	2780	lime brkn	4449		
shale & shells	2815	lime cherty	4490		
lime & shale	2865	lime	4528		
lime brkn	2880	shale	4547		
shale	2905	cored	4569		
lime	2932	CABLE			
shale	2950	Total Depth in sand	4569		
lime	3008				
lime brkn	3012	Tops:			
lime	3026	Ft. Riley	2068		
lime & shale	3093	Douglas (tested 1 M.G.)	3764-84		
lime brkn & shale	3140	Kansas City	3809		
lime brkn	3164	Mississippi	4307		
lime	3184	Kinderhook	4365		

DEEPENING RECORD:

Company - National Coop. Refy Assn.
Farm - Gant "A" # 2
Comm. 8-19-47 Comp. -9-5-47
Production - SWDW
Total depth - 4761
Old Total Depth 4569
Lime 4579
sand & shale 4587
sand hard, & shale 4593
shale 4622
lime 4629
lime & shale 4651
lime & chert 4666
lime 4742
lime cherty 4755
lime 4761
Total Depth