

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


20-31-13W

Company- GRAYBOL OIL CORP.  
Farm- Mills No. 1

SEC. 20 T. 31 R. 13W  
C NW SW

Total Depth. 4566'  
Comm. 10-6-64 Comp. 10-24-64  
Shot or Treated.  
Contractor. Co. Tools  
Issued. 1-9-65

County Barber  
KANSAS



Elevation. 1575 DF

Production. Dry

CASING:

8 5/8" 286' pozmix cem.  
w/200 sx.

Figures Indicate Bottom of Formations.

Sand & Red Bed	80
Red Bed	140
Red Bed, Shale & Shells	695
Red Bed & Shale	1015
Shale & Shells	1715
Lime & Shale	2625
Shale & Lime	3165
Lime & Shale	3250
Lime	3325
Lime & Shale	3485
Shale & Lime	3740
Lime	4155
Lime & Shale	4181
Lime	4370
Shale & Lime	4406
Lime	4467
Cherty Lime & Shale	4481
Lime & Shale	4518
Lime, Shale & Sand	4555
Shale	4566
Total Depth	

TOPS-Electric	
Stone Corral Anhydrite	506
Heebner Shale	3562
Lower Douglas Sand	3701
Brown Lime	3726
Lansing Limestone	3742
Base Kansas City	4162
Marmaton Limestone	4183
Reworked Mississippian	4234
Mississippian	4297
Kinderhook Shale	4328
Chattanooga Shale	4383
Viola Limestone	4396
Simpson Shale	4497
Simpson Sand	4520

DST #1 4285-4310. Op. 1 hr.  
Rec. 20' drilling mud. I &  
FBHP-45#/30", I&FFP-45#.  
BHT. 111 deg.