

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-007-20712

KANSAS DRILLERS LOG

API No. 15 — 007 — 20,712
County Number

Operator

Texas Oil & Gas Corp.

Address 300 - 200 West Douglas Wichita, Kansas 67202

Well No.
#1

Lease Name
Stonestreet "A"

Footage Location

2310 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor

Slawson Drilling, Inc.

Geologist

Charley V. Shank

Spud Date

1-15-79

Total Depth

4270'

P.B.T.D.

~~4876'~~ 4233'

Date Completed

2-11-79

Oil Purchaser


Permian

S. 25 T. 31 R. 13 W

Loc. 2310' FSL & 330' FWL

County Barber

640 Acres
N



Locate well correctly

Elev.: Gr. 1524'

DF KB 1529'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	313'	Lite-weight Common	100 200	2% Gel, 3% CaCl
Production		4 1/2"		4257'	Common	250	2% Gel, 3% CaCl

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
N/A	N/A	N/A

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	Deep Penet.	4162-72'

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	4220'	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1,250 gal. acid; 31,000 GW; 46,500# sd	4162-72'

INITIAL PRODUCTION

Date of first production 2-11-79		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 112 bbls.	Gas N/A MCF	Water 99 bbls.	Gas-oil ratio N/A CFPB	
Disposition of gas (vented, used on lease or sold) N/A			Producing interval(s) 4162-72' (Mississippi)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody
is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

erator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Texas Oil & Gas Corp.

Well No. 1	Lease Name Stonestreet "A"	Oil Well		
S <u>25</u> T <u>31</u> S <u>R</u> <u>13</u> W <u>A</u> W				
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	1782	-253		
Cottonwood	2338	-809		
Indian Cave ss	2578	-1049		
Heebner	3485	-1956		
T/Douglas Group	3522	-1993		
U/Douglas ss	3532	-2003		
L/Douglas ss	3646	-2117		
Lansing	3665	-2136		
Swope	4006	-2477		
Hertha	4048	-2519		
Mississippi	4161	-2632		
TD	4270	-2741		
PBTD	4876 4233	-3347 -2704		
DST #1, 4166-97', (Mississippi) w/results as follows:				
IFP/30": 62-53#, fair to good blow				
ISIP/60": 1317#				
FFP/45": 63-53#, strong blow				
FSIP/90": 1506#				
Rec 900' gas in pipe, 1261' SGC oil spkd mud, 75% mud, 15% wtr, 5% oil.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	 HAROLD A. BROWN District Geologist March 8, 1979			
	Signature Title Date			

OPERATOR: Texas Oil & Gas Corp.
200 W. Douglas, Suite 300
Wichita, Kansas 67202

LEASE: Stonestreet 'A' No. 1
NW NW SW Sec. 25-31S-13W
Barber County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 1/15/79

COMPLETED: 1/24/79

RTD: 4270'

SURFACE CASING: 8-5/8" set at 313' with 300 sx cement

OIL STRING: 4-1/2" set at 4259' with 250 sx cement

0' to 318' 12 1/4" Surface Hole
318' to 590' Red Bed
590' to 1685' Shale
1685' to 1927' Shale with lime strks.
1927' to 2360' Shale & Lime
2360' to 3510' Lime & Shale
3510' to 3663' Shale & Lime
3663' to 3955' Lime & Shale
3955' to 4270' Lime
RTD 4270'

RECEIVED
STATE CORPORATION COMMISSION


FEB - 6 1979

STATE OF KANSAS

CONSERVATION DIVISION
Wichita, Kansas

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state that the above and foregoing is an accurate copy of the
Stonestreet 'A' No. 1 log for Texas OIL & Gas Corp.


James C. Remsberg

Subscribed and sworn to me this 2nd day of February 1979