

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 007 — 21,174  
County Number

S. 28 T. 31 R. 13 <sup>XY</sup><sub>E</sub>  
W  
Loc. 1980' FNL & 660' FEL

County Barber County

Operator

Texas Oil & Gas Corp.

Address

200 W. Douglas, Suite 300, Wichita, KS 67202

Well No.

#1

Lease Name

Thom "D"

Footage Location

1980' feet from (N) ~~XX~~ line 660' feet from (E) ~~XX~~ line

Principal Contractor

H-30, Rig #3

Geologist

Professional Well Logging

Spud Date

5-19-81

Date Completed

5-29-81

Total Depth

3780'

P.B.T.D.


N/A

Directional Deviation

Not directionally drilled

Oil and/or Gas Purchaser

N/A



Locate well correctly

Elev.: Gr. 1573

DF \_\_\_\_\_ KB 1581

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	298'		300	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	N/A	N/A	N/A

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production D & A, 5-29-81		Producing method (flowing, pumping, gas lift, etc.) dry			
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls.	Gas N/A MCF	Water N/A bbls.	Gas-oil ratio N/A	CFPB
Disposition of gas (vented, used on lease or sold) Dry & Abandoned			Producing interval (s) N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

FIELD: Nurse Ext.

Operator: Texas Oil & Gas Corp. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole

Well No. #1 Lease Name Thom "D"

S 28 T 31 R 13 <sup>EX</sup> W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Herington	1827	-246		
Winfield	1893	-312		
Towanda	1962	-381		
Florence	2012	-431		
Wreford	2203	-622		
Cottonwood	2316	-735		
Indian Cave	2620	-1038		
Wabaunsee	2662	-1081		
Topeka	2995	-1414		
Heebner	3549	-1968		
Toronto Ls	3556	-1975		
U. Douglas ss	3616	-2035		
Lansing	3731	-2150		
TD	3780	-2199		
Ran O.H. Logs				
DST #1, 2585' - 2644' (Ind. Cv), severe plugging, no pressures & no recovery.				
DST #2, 2583' - 2644', (Ind. Cv), w/results as follows:				
IFP/20": plugging				
ISIP/90": plugging				
FFP/45": 104-187#, good blow				
FSIP/90": 1039#				
Rec: 300' GCW				
DST #3, 3598' - 3640', (Upper Douglas), w/results as follows:				
IFP/30": 206-481#				
ISIP/60": 1316#				
FFP/45": 527-797#				
FSIP/90": 1316#				
Rec: 1516' SW				
DST #4, 3672-3700' (Lower Douglas), w/results as follows:				
IFP/30": 41-160#, good blow				
ISIP/60": 1339#				
FFP/45": 183-252#				
FSIP/90": 1339# Rec: 180' MW, 370' SW				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received  
 DST #5, 3364-75' (Lacompton), w/results as follows:  
 IFP/30": 54-68#, weak incr. to fair blow  
 ISIP/60": 1268#  
 FFP/45": 81-95#  
 FSIP/90": 1268#  
 Rec: 60' GIP + 60' OSW + 120' SW  
 (10% oil, 20% gas, 17% mud, 53% wtr)

  
 Harold R. Trapp Signature  
 District Geologist  
 Title  
 May 29, 1981  
 Date

KANSAS DRILLERS LOG

COMPANY Texas Oil and Gas Corporation

SEC. 28 T. 31S R. 13W  
LOC. 1980' FNL and 660' FEL

FARM Thom "D" NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 3780'

COMM. May 19, 1981

COMP. May 29, 1981

CONTRACTOR H-30, INC.

ISSUED June 10, 1981

CASING

10 3/4"

8 5/8" 298' Cemented w/ 300 sxs cement

ELEVATION 1,573 gr

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	300'
Red Bed and Shale	1035'
Shale	1715'
Shale and Lime	2644'
Lime and Shale	3780'
RTD	3780'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
\_\_\_\_\_  
Dean Britting

State of Kansas )  
                  ) SS  
County of Sedgwick )

Subscribed and Sworn to before me, a Notary Public, in and for