


30-31-13W

County Barber

KANSAS



Total Depth. 4665
Comm. 4-24-52 Comp. 5-20-52
Shot or Treated.
Contractor. R. C. Patton Co.
Issued. 6-14-52

CASING:

12 1/2" 200' cem. w/275 sx

Elevation. 1591

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	25
sand	32
shale red & shells	200
shale red	221
shale & shells	1250
shale & salt	1335
shale	1360
shale & shells	1600
anhydrite & shale	1825
shale & lime	3731
sand	3745
shale & lime	3970
lime	4139
shale & lime	4173
lime	4195
shale & lime	4262
shale	4274
shale & lime	4297
shale	4328
chert	4345
chert & lime	4361
lime	4396
shale & lime	4445
chert & lime	4541
shale & lime	4575
shale & sand	4625
sandy shale	4637
lime	4665
Total Depth	

Tops:	
Topeka	2869
Heebner	3579
Toronto	3597
Lansing-K. C.	3752
Miss.	4250
Kinderhook	4366
Simpson	4541
Arbuckle	4636

DST: #1 4329-4345' tool open
20 mins. rec. 20' of rotary
mud. 15 min. shut-in bottom
hole pressure 50# PSI.
DST: #2 4465-4480' tool open
35 mins. weak blow for 20
mins. rec. 30' of rotary & with

few specks of oil. 15 min shut-in
bottom hole pressure 125 # PSI.