


31-31-13W
 County Barber

KANSAS

Total Depth. 4745'
 Comm. 11-26-55 Comp. 12-13-55
 Shot or Treated.
 Contractor. Aylward Drlg. Co.
 Issued. 2-25-56



CASING:
 8 5/8" 140' cem w/125 sx

Elevation. 1606' RR

Production. Dry

Figures indicate Bottom of Formations.

red bed	30
sand	70
red bed, lime,	
shells	140
red bed	575
anhydrite	590
shale & shells	1260
salt	1340
shale, shells, lime	
strks	1555
shale, shells	1650
lime	1745
lime & shale	1885
lime & shale strks	2020
hard lime	2110
lime & shale	2230
lime	2325
lime & shale	3755
shale & sand	3781
sand & lime	3820
lime	3903
lime & shale	4055
lime	4104
lime & shale strks	4171
lime & shale	4270
lime	4423
lime & shale	4465
lime	4501
lime & shale	4546
lime	4602
cherty lime	4649
lime & shale	4680
sand & shale	4722
lime	4745
Total Depth	

DST #1 3750-3772' open 1 1/2 hr., Rec. 580'
 salt water, FP 60-340# BHP 1480#/30 min.,
 HP 2030#/10.1# mud, Temp. 126 dep.

DST #2 4725-4745', open 1 1/2 hrs., strong blow
 Rec. 1930' sulphur water, FP 80-950#,
 BHP 1670# in 30 min.

Tops:	
Heebner	3612
Toronto	3624
Base Oread	3648
Sand	3739
Lansing	3783
Base Kansas City	4198
Des Moines	4211
Mississippi	4314
Kinderhook	4412
Chattanooga	4503
Viola	4521
Simpson	4633
Arbuckle	4722