

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

1-31-14W


Company
Farm

DRILLERS GAS CO.
Pearl Lake No. 1.

SEC. 1 T. 31 R. 14 W.
CW $\frac{1}{2}$ SW SW

Total Depth. 4409 $\frac{1}{2}$
Comm. 8-22-45 Comp. 10-7-45
Shot or Treated. 1000 Acid
Contractor. R.C. Patton Co.
Issued. 1-12-46

County. Barber
KANSAS



CASING:
10 $\frac{3}{4}$ " 688' Cem.
7" 4401' Cem.

Elevation. 1700 $\frac{1}{2}$

Production. 5,000,000 cu.ft.
after acid

Figures Indicate Bottom of Formations.

red bed & shells	600	Tops:	
red bed	623	Douglas	3787
anhydrite	642	Lansing	3823
red bed & shale	1100	Miss.	4322
salt & shale	1265	Maquoketa	4400
shale & shells	1733		
lime	1763		
shale & lime	1810		
lime	1850	I.P. 5,000,000 cu.ft. Gas	
shale & lime	1915	after 1000 acid	
lime	2105		
shale & lime	2183		
lime	2225		
shale & lime	2453		
lime	2482		
shale & lime	2533		
shale	2547		
shale & shells	2715		
lime & shale	2834		
shale & shells	2922		
shale & lime	2960		
lime	3084		
lime & shale	3160		
lime	3290		
lime & shale	3460		
lime	3540		
shale & lime	3610		
lime	3617		
lime & shale	3703		
sand	3725		
shale	3768		
shale & lime	3788	lime chat	4157
sand	3810	lime chert	4189
shale	3827	lime shale	4200
shale & shells	3887	lime	4315
lime	3898	shale	4319
cherty lime	3910	lime & shale	4341
lime	3939	lime	4367
shale & lime	4016	shale	4401
lime	4080	Viola lime	4409 $\frac{1}{2}$
cherty lime	4099	Total Depth	
lime	4121		