

4-31-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. STANOLIND OIL AND GAS COMPANY
Farm. Dorothy V. Hargis "C" No. 1

SEC. 4 T. 31 R. 14W
NE SW SE
330' SN1 & 330' WE1 SE1

Total Depth. 4460'
Comm. 7-6-47 Comp. 8-20-47
Shot or Treated. Acid. w/5000 gals.
Contractor.
Issued. 10-11-47

County. Barbor
KANSAS



Elevation. 1717

Production. 15,638,000 Gas

CASING:

13-3/8" 203' Com. w/225 sx
5-1/2" 4455' Com. w/400 sx

Figures Indicate Bottom of Formations.

collar	0-12	Tops:	
rod bed & clay	35	Viola	4455
sand	43	Maquokota	4396-4420
rod bed, sand & gravel	204		
rod bed	440		
rod bed & shale	580		
shale w shells	710		
limo sdy	740		
anhydrite w shale	755		
shale	800		
rod bed	870		
anhydrite w/shale and shells	945		
shale w shells	1120		
shale & limo	1310		
shale	1340		
salt	1460		
shale	1575		
limo & shale	1960		
limo	2090		
limo w shale	2435		
limo	2475		
shale w limo	2675		
shale	2735		
shale & limo	2835		
lime	2875		
limo & shale	3235		
limo brkn	3380		
lime & shale	3480		
lime	3550		
lime sdy	3660		
lime	3710		
shale & sand	3765		
lime sdy w shale	3845		
limo	3940		
sand & limo	4030		
limo	4358		
shale	4401		
limo, shale & dolomite	4410		
dolomite	4460		
Total Depth			

Ran Schlumberger (T.D. 4459)
Set Lane Wells Bridge Plug @ 4430'.

Perf. casing @ (96 shots) 4396 - 4420'.

Ran tubing and acid. w/2000 gals @ 4426.
Tested 5,700,000 Gas through 2" tubing.
Acid. w/5000 gals.
Test showed 15,638,000 Gas per 24 hrs.
no oil, no water.