


Company - DRILLERS GAS CO.  
 Farm - D. W. Skinner No. 1

SEC. 8 T. 31 R. 14 W  
 CW/2 SE SW

Total Depth. 4408'  
 Comm. 5-21-45 Comp. 6-17-45  
 Shot or Treated.  
 Contractor. R. C. Patton Co.  
 Issued. 8-4-45

County. Barber  
 KANSAS



Elevation. \_\_\_\_\_  
 Production. Pot. 7,563,000 G.

CASING:

13" 183' Cem.  
 8 5/8" 672' Cem.  
 5 1/2" 4406' Cem.

Figures Indicate Bottom of Formations.

cellar	8
sand & gravel	65
sand	141
sand & red bed	183
red bed	360
red bed & shells	505
red bed	530
anhydrite	535
red bed	635
anhydrite	650
shale	725
red bed	730
red bed & shells	1000
shale & shells	1425
lime & shale	1550
shale & salt	1610
shale & lime	1830
lime	1947
shale & lime	2160
sand sharp	2170
lime sdy	2210
shale & lime	2260
shale & shells	2300
shale & lime	2390
shale & shells	2595
lime sft	2620
shale & lime	2682
lime	2715
shale & lime	2938
lime	2998
shale & lime	3168
shale & sft lime	3266
shale & lime	3749
lime	3801
shale & lime	3850
lime K.C.	3878
lime & chert	3936
lime	4237
lime & chert	4270
shale	4293
shale	4321
lime	4408
Total Depth.	

