

9-81-14W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company J. M. HUBER CORP. & CITIES SERVICE OIL
Farm Mills No. 1 CO.

SEC. 9 T. 31 R. 14 W
NW SW SW

Total Depth. 4370'
Comm. 5-20-46 Comp.
Shot or Treated.
Contractor. J. M. Huber Corp.
Issued. 8-17-46

County. Barber
KANSAS



Elevation. 1629 *nh*

Production. Pot. 1418 B.

CASING:

15 1/2" 99' Cem.
10" 792' Cem.
5 1/2" 4360' Cem.

Figures Indicate Bottom of Formations.

sand	65
red bed & shells	115
red bed	140
red bed, shale & shells	805
shale & shells	1190
salt, shale & shells	1410
shale & shells	1680
lime shells & shale	1860
lime & shale	1910
shale & lime shells	1965
lime & shale	2155
lime brkn	2175
lime	2190
lime brkn & shale	2300
lime	2350
lime & shale	2435
lime & shale brks	2535
lime & shale	3020
lime brkn & shale strks	3125
lime brkn	3580
lime & shale	3715
lime	3735
lime & shale	3865
lime	3900
lime brkn	3975
lime	4060
lime & shale	4095
lime	4255
lime & shale	4320
lime & shale strks	4360
dolomite	4370
Total Depth.	

Maquoketa 4334
Porous Dolomite 4360

Loaded hole, drld plug & cleaned out to 4370' Td. Ran 2" tbg. & unloaded hole by swbg through tbg. Swbd 2 to 2 1/2 BOPH. Treated w/500 gals. acid. Flowed into tanks 150 BO in 3 hrs.

Tops:
Lansing 3756
Conglomerate cherty 4270