

9 - 31 - 14W


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE DRILLERS GAS COMPANY  
Farm - H. W. Skinner No. 2

SEC. 9 T. 31 R. 14W  
SW NE SE

Total Depth. 4408' PB 4337'  
Comm. 7-15-46 Comp. 10-19-46  
Shot or Treated. Acid.  
Contractor. R. C. Patton Co.  
Issued. 7-26-47

County. Barber  
KANSAS



Elevation. 1628 rh.  
1682 rh.

Production. Pot. 188 BOPD & 5%  
water

CASING:

15 1/2" 84'  
12 3/4" 261' Com. w/169 sx  
8 3/4" 785' Com. w/125 sx  
5 1/2" 4326' Com. w/250 sx

Figures Indicate Bottom of Formations.

|                          |      |
|--------------------------|------|
| sand                     | 60   |
| red beds                 | 74   |
| shale red                | 255  |
| red beds & shells        | 475  |
| shale, red beds & shells | 521  |
| shale & shells           | 710  |
| shale & red beds         | 1020 |
| shale & shells           | 1250 |
| salt                     | 1320 |
| shale & shells           | 1460 |
| shale & lime             | 2045 |
| lime                     | 2090 |
| shale & lime             | 2177 |
| lime                     | 2390 |
| lime brkn                | 2465 |
| shale & lime             | 2970 |
| lime brkn                | 3025 |
| lime                     | 3178 |
| lime brkn                | 3305 |
| lime & shale             | 3488 |
| lime                     | 3547 |
| lime & shale             | 3665 |
| lime                     | 3720 |
| sand                     | 3741 |
| lime                     | 3885 |
| chert & lime             | 3935 |
| lime                     | 4054 |
| lime cherty              | 4080 |
| lime                     | 4133 |
| lime & shale             | 4170 |
| lime                     | 4256 |
| lime & shale             | 4284 |
| lime                     | 4328 |
| shale                    | 4361 |
| lime                     | 4359 |
| shale green              | 4361 |
| shale                    | 4366 |
| shale green chert        | 4371 |
| shale & chert            | 4373 |
| shale                    | 4374 |
| shale & chert            | 4375 |

Well reworked by R. C. Patton Co.  
as Patton Drillers.

Shot w/ 10 qts. Nitro  
Swab 43 BO in 40 hrs.  
4000 gals. acid.

|                   |      |
|-------------------|------|
| shale green & blk | 4370 |
| shale             | 4382 |
| lime              | 4386 |
| chert & lime      | 4408 |
| Total Depth       |      |

Plugged back to 4337'

|         |      |
|---------|------|
| Tops:   |      |
| Douglas | 3722 |
| Lansing | 3755 |
| Viola   | 4325 |

@ 4366' 20' oil in hole in  
12 hrs.  
2000 gal. acid  
1000' oil in hole in 12 hrs.  
Swab 22 BO in 6 hrs.