

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company. DRILLERS GAS CO.
Farm. Pearl Lake "B" No. 1

SEC. 11 T. 31 R. 14 W
CE/2 NW NE

Total Depth. 4383½'

Comm. 6-17-46


Comp. 7-29-46

Shot or Treated. Acidized

Contractor.

Issued. 9-14-46

County. Barber
KANSAS



Elevation. 1677²⁴

CASING:

10 3/4" 812' Cem.
7" 4377' Cem.

Production. 3,000,000 Gas

Figures Indicate Bottom of Formations.

shale red & shells	60
red bed & sand	170
shale & red bed	315
shale red	515
shale red & shells	606
shale & shells	818
shale red & shells	1115
shale & shells	1300
salt & shale	1390
shale & shells	1720
lime & shale	1800
shale & anhydrite	1890
lime	1980
lime & shale	2070
lime	2095
shale	2160
lime sdy	2235
lime	2400
lime & shale	2415
shale	2450
lime & shale	2690
shale	2822
lime & shale	2870
shale	2930
lime & shale	3130
lime	3169
lime & shale	3218
lime sdy	3266
lime	3360
lime & shale	3450
shale	3463
lime	3523
shale	3552
lime	3637
shale	3675
lime & shale	3687
shale	3715
sand	3728
lime	3738
lime & shale	3755
shale	3772
sand	3785

Tops:
Douglas 3772
Aquoketa 4377

Gauge 242,000 Natural

1000 gal. acid Gauge 1,265,000 cu.ft.

2000 gal. acid Gauge 2,000,000 Cu.ft.

5000 gal. acid Gauge 3,000,000 cu.ft.

shale	3822
lime	3894
shale	3918
lime	4088
lime & shale	4099
lime	4210
lime brkn	4243
lime	4260
lime & shale	4278
lime	4295
lime sharp rough	4312
shale	4350
shale & lime	4376
lime Viola	4383½
Total Depth.	