

17-31-14W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - J. M. HUBER CORP.


Farm - Skinner

No. 2

SEC. 17 T. 31 R. 14W
SE NE NW

Total Depth. 4376'
Comm. 8-17-48 Comp. 9-6-48
Shot or Treated.
Contractor. Coppinger and Southern
Issued. 10-23-48

County. Barber
KANSAS



CASING:

16" 160' cem w/125 Sx.
8 5/8" 810' cem w/400 Sx., circulated to surface
5 1/2" 4363' cem w/150 Sx., circulated to surface
Figures Indicate Bottom of Formations.

Elevation. 1639' Ind.

Production. 3,000 Bbls.

sand	40
clay	65
s nd	160
shale	265
sh le & shells	350
red bed	540
shale	640
shale & shells	1220
salt	1425
shale	1735
lime	1960
lime & shale	2190
lime	2425
lime & shale	2560
sh le	2835
lime & shale	2985
lime	3305
shale	3320
lime	3440
shale	3585
lime	3620
shale	3655
lime sdy	3690
sh le & lime	3750
lime	4144
shale	4175
lime	4376
total depth	

Tops:

Viola 4334'