

17-31-14W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


Company - COPPINGER & SOUTHERN ETAL
Farm - Skinner "B" No. 2

SEC. 17 T. 31 R. 14W
SW SE NW

Total Depth. 4423
Comm. 10-13-48 Comp. 11-23-48
Shot or Treated.
Contractor. Coppinger and Southern
Issued. 2-26-49

County. Barber

KANSAS



Elevation. 1674 *Ind.*

Production. Pot 3000 bbl.

CASING:

8 5/8" 852' cem w 500 sx.
5 1/2" 4406' cem w/200 sx.

Figures Indicate Bottom of Formations.

sand	415
shale, shells	1340
salt	1450
shale, shells	1560
lime	1670
shale, lime	1835
lime	2290
lime, shale	2365
shale	2375
lime, shale	2445
lime	2550
lime, shale	2755
shale, lime	3025
lime	3050
shale, lime	3120
lime	3691
lime, shale	3815
lime	4370
shale	4381
viola lime	4406
lime	4423
total depth	

Tops:

Douglas Sand	3795
Kansas City	3820
Kinderhook-	4347
Maquokata	4378
Alyn Dolomite	4401-3