

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


DEEPENING RECORD:

Company. BISHOP OIL CO. & J.M. HUBER CORP.
Farm. Skinner "C" No. 1

SEC. 17 T. 31 R. 14W
NE SE

Total Depth. 4440'
Comm. 10-16-46 Comp. 12-23-46
Shot or Treated. Acid.
Contractor. J. M. Huber Corp.
Issued. 2-19-49

County. Barber
KANSAS



Elevation. 1657 feet.

Production. 11,900,000 Gas, ...

CASING:

10" 709'
8" 880'
4 1/2" 4367' Com w/125 sx

Figures Indicate Bottom of Formations.

red clay shells	90
red bed shells	120
red bed, shale & shells	565
shale & shells	1175
salt & shells	1440
shale & shells	1720
lime, brn lime & shale	
strks	1870
lime & shale	2410
lime & shale strks	2470
shale & shells	2930
shale & lime	3000
lime & shale	3110
limo	3130
lime & shale	3405
brn lime	3550
limo & shale	3620
lime, shale, & sand	3700
sdv shale & limo shells	3730
lime & shale	3765
shale & lime	3830
lime & shale	3990
lime	4085
limo & shale strks	4125
limo	4185
limo & shale	4315
shale	4364
limo sft Maq.	4395
Total Depth	

Tops:
Lansing 3796
Miss. Chert 4302
Maquoketa 4364

Drilled the plug & GO to RTD
4395. Ran tubing & unloaded hole.
Gauged 1,000 MCF natural, washed
with 300 acid, treated with 3,000 acid
& gauged 7,000 MCF with spray of oil &
acid water. After blowing several hours
shut well in 10 hours, built up 1200" top
pressure.

After 10 minute blow down gauged 15,000 MCF

After 20 minute blow down gauged 10,900 MCF

Deepening Record:

Deepened by: Bishop Oil & J. M. Huber Corp.
Deepening Commenced: 12-1-48
Deepening Completed: 12-9-48
Production: Pot. 41 BO 9 1/2 wtr.

Swabbed 10 BPH & est. 400,000 CFG
Squeezed 25 sxs. com. 4367-95
limo 4395' to 4440'

Top Course: vlyn Viola 4428
SFO & wtr. 4431-4440
Swab. 5 BPH & 4 BO/5hrs.
500 gal acid. 4431-40 / Dowell Pilot
Swab 40 BO & 22 1/2 hrs. 2000' off bottom
Pot. 41 BO plus 9 1/2 wtr.