


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BISHOP & HUBER
Farm - Skinner "C" No. 2

SEC. 17 T. 31 R. 14W
N. c SE

Total Depth. 4397
Comm. 2-149 Comp. 2-6-49
Shot or Treated.
Contractor. J. M. Huber Corp.
Issued. 6-25-49

County. Barber
KANSAS



Elevation. 1654 *ft*

Production. 70 BOPD 5% wtr.

CASING:

16" 140 w 300 sx.
5 1/2" 4362 w 250 sx.

Figures Indicate Bottom of Formations.

sandy red beds, shells & sand	10
sand & shales	60
shale & shells	140
red bed & hulls	335
red bed & shells	807
shells & shales	1170
salt, shale & shells	1405
shale & shells	1635
lime & shale	1755
shale & lime	1845
lime & shale breaks	2010
lime & shale	2425
shale & lime shells	2520
shale & lime	2700
lime, shells & shale	2805
shale & lime	3105
lime & shale breaks	3175
lime & shale streaks	3245
sand & lime	3335
shale & lime	3390
lime brkn & shale streaks	3475
lime & shale	3660
shale & shells	3680
lime brkn	3740
shale & lime	3827
lime	3846
lime with shale streaks	3913
lime & shale	3948
lime & shale breaks	3998
lime	4074
lime & chert	4092
cherty lime	4113
lime	4165
lime & shale streaks	4193
lime & shale	4262
lime cherty	4294
shale & lime	4325
shale	4366

RTD		4366
Shale?	TD	4397

Sample Tops:
Viola 4359-66 RTD

Took Drill Stem Test 3626-45, open 20 minutes, recovered 60' mud.
Set 5 1/2" at 4362 with 250 sx. Drilled plug and drilled deeper to 4371. Swabbed 2 barrels oil and 1 barrel water per hour. Acidized with 600 gallons. Flowed 34 barrels oil plus 5 barrels water/14 hours. Total Depth 4397. Flowing 22 barrels oil/7 hours. Physical potential 70 barrels oil per day plus 5% water.