

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
508 E. Burdock, Wichita, Kansas


Company - J. M. HUBER CORP.  
Farm - Skinner No. 3

SEC. 17 T. 31 R. 14W  
SE NW NW

Total Depth. 4390  
Comm. 1-1-49 Comp. 2-23-49  
Shot or Treated.  
Contractor. J. M. Huber Corp.  
Issued. 10-8-49

County. Barber

KANSAS



Elevation. 1649 *ft*

CASING:  
16" 90' w/125 sx.  
10" 800' w/500 sx.  
5 1/2" 4377' w/300 sx.

Production. 264 bbls oil / 4%  
wtr. / 24 hrs.

Figures Indicate Bottom of Formations.

red bed & shells	740
shale & shells	915
red bed, shale & shells	1555
shale & lime	1970
lime, brkn	2050
lime, shale strks	2135
shale & lime	2170
cherty lime	2188
shale	2205
lime & shale brks	2270
shale & lime	2715
lime brn shale	2825
lime & shale	3040
lime brkn	3120
lime & shale	3180
lime	3320
lime & shale	3515
lime sdy	3567
lime & shale	3820
shale & lime	3893
lime & shale brks	3940
lime & shale	4020
lime	4200
lime & shale	4340
shale	4352
lime	4398
Total Depth	
Tops:	
Viola	4359

4398 T. 3615-25 - upon 15 mins., gas in 9 mins.  
rec. 60' of wtr, estimated 2 to 3,000,000 gas  
est. bottom hole pressure 1360%.  
Viola 4359c, Correction...4380 equals 4387 R.T.I.  
by strapped drill pipe. Drilled plug &  
cleaned out to rotary total depth 4387'.  
Tested 1/2 bbl. oil per hr., washed w/200 gal  
acid. Cleaned out, tested 1 1/2 bbl oil per hour,  
1000 gals. acid w/pilot 4379-87 (on vacuum)  
Sec. load 25 bbls oil, fluid level standing  
at 1200' & casing press. 300%. Flowed 4 1/2-5  
bbls oil per hour, 1% wtr & 1% basic sediment/  
22 hours. Killed well w/60 bbls oil & drilled  
deeper to 4398. Swabbed load & well flowed  
4 bbls oil per hour/13 hours, 1% basic sediment  
& trace wtr, 20.0 acid, & flowed 64 bbls oil/5hrs.  
2% basic sediment. Shut down overnight &  
flowed 70 bbls oil/4 hours. Flowed potential  
264 bbls oil/24 hrs. / 4% wtr.

