

17-31-14W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - J. M. HUBER CORP.
Farm - Skinner "H" No. 2

SEC. 17 T. 31 R. 14W
NE NW SW

Total Depth. 4444
Comm. 9-1-48 Comp. 10-15-48
Shot or Treated.
Contractor. J. M. Huber Corp.
Issued. 6-25-49

County. Barber KANSAS



Elevation. 1697 Ind

Production. 1785 bbls plus
30% wtr.

Figures Indicate Bottom of Formations.

red bed & shells	550
shells & red bed	840
shale, shells & red bed	1075
salt shale & shells	1275
salt, lime & shale Breaks	1645
shale & shells	1775
lime & shale breaks	1935
lime & shale	2020
lime	2120
lime & shale	2220
cherty lime	2245
shale & lime	2300
lime shale	3160
lime & shale streaks	3210
lime & shale	3470
lime brn sandy	3585
lime & shale	3680
lime	3740
lime & shale	3850
lime	3890
lime & shale	3985
lime	4045
lime & shale	4083
lime	4204
lime & shale	4400
lime	4440
Lime ? RTD TD	4444

Sample Tops:
Lansing 3841
Viola 4408

5 1/2" at 4438' with 200 sx. Drilled cement and
drilled deeper to 4444, total depth and scrubbed
3 1/2-4 barrels per hour/8 hours, natural.
Filled up with 2200' oil in hole/20 hours.

Acidized with 1000 gallons and scrubbed 276 barrels
oil/8 hours. Flowed 27 barrels oil per hour/8 hours
through 1" choke; 24.86 barrels oil per hour/8 hours
through 45/64" choke and 27.22 barrels oil per
hour/8 hours through 3/4" choke. Bottom hole bomb
potential--176 barrels oil plus 30% wtr. Bottom
hole Pressure 640#. COMPLETE