

17-31-14W

## WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

Wichita, Kansas


Company - J. M. HUBER CORPORATION  
 Farm - Skinner "H" No. 3

SEC. 17 T. 31 R. 14W  
 NE NE SW

Total Depth. 4392  
 Comm. 12-8-48 Comp. 3-16-49  
 Shot or Treated. 1000 gals. acid  
 Contractor. J. M. Huber Corp.  
 Issued. 11-19-49

County. Barber

KANSAS



CASING:  
 8" set @ 840' w/425 sx.  
 5" set @ 4380' w/200 sx.

Elevation. 1661 *sd*

Production. 88 BO Plus 20% wtr.

Figures Indicate Bottom of Formations.

|                        |      |
|------------------------|------|
| Red bed & shells       | 1275 |
| Salt, shale & shells   | 1565 |
| Shale & shells         | 1725 |
| Lime & shale           | 1935 |
| Lime                   | 1995 |
| Lime & shale           | 2095 |
| Shale & lime           | 2175 |
| Lime                   | 2225 |
| Lime & shale           | 2500 |
| Lime & shale streaks   | 2595 |
| Shale                  | 2685 |
| Lime & shale           | 3045 |
| Lime & shale streaks   | 3145 |
| Lime & shale           | 3460 |
| Shale                  | 3495 |
| Lime                   | 3530 |
| Broken lime & shale    | 3615 |
| Lime & shale           | 3695 |
| Lime shaley            | 3775 |
| Shale & lime           | 3799 |
| Sand                   | 3810 |
| Shale & lime           | 3893 |
| Lime & shale breaks    | 3939 |
| Lime broken, shale str | 4009 |
| Lime                   | 4315 |
| Shale & lime shells    | 4345 |
| Shale                  | 4375 |
| Lime                   | 4392 |

Total Depth

FORMATION TOPS

Viola 4367

C.O. to R.T.D. washed w/200 gal. acid.  
 § 1 BOPH. 1000 gals. acid 4381-92½.  
 Flowed 33.88 BF/2 hrs;  
 " 107 BF/8 hrs. 25% wtr.  
 Pumped 11 BF/22½ hrs., 20% wtr.