

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

18-31-14W


Company- HINKLE OIL COMPANY
Farm- Shaft No. 1

SEC. 18 T. 31 R. 14W
SW SE SW

Total Depth. 4805'
Comm. 12-30-64 Comp. 1-17-65
Shot or Treated.
Contractor. Sierra Pet. Co.
Issued. 3-20-65

County Barber

KANSAS



Elevation. 1802 KB

Production. Dry

CASING:

8 5/8" @ 893' cem w/700 sx
5 1/2" @ 4802' cem w/150 sx

Figures Indicate Bottom of Formations.

surface clay	25
red bed	150
red bed & shale	738
red bed	898
red bed & shale	1740
Anhydrite	1770
shale & lime	2045
lime	2450
lime & shale	3250
lime	3871
lime & sand	3956
lime	4605
lime & chert	4651
lime & sand	4680
lime & sand	4691
sand	4777
lime	4805
Total Depth	4805

TOPS: Scout

*Tarkio	3080
Heebner	3790
*Lower Douglas sand	3947
Lansing	3962
*Massy	4419
Mississippi	4480
Viola	4544
Simpson sand	4675
Arbuckle	4798

*Sample tops