

23-31-14W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. AYLWARD DRILLING CO.
Farm. Lake "C" No. 1-A

SEC. 23 T. 31 R. 14W
NW NW NW

Total Depth. 4618'
Comm. 6-28-58 Comp. 7-13-58
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 5-2-59

County Barber
KANSAS



CASING:

8 5/8" 846' cen w/450 sx.

Elevation. 1618' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	20
sand	45
red rock & shale	435
red bed & shale	935
salt	935
shale & lime	1315
shale & shells	1575
shale & lime	1735
lime w/shale strks	1965
lime	2115
lime w/some shale	2300
lime	2575
lime & shale	2800
shale & lime	2950
lime & shale	3100
lime	3355
lime & sandy shale	3500
lime & shale	3718
sand	3730
sandy shale & lime	3745
lime & shale	3845
lime	4241
lime w/some shale	4270
cherty lime	4303
chert & lime	4340
cherty lime	4355
lime & shale	4382
lime	4416
lime (cherty)	4487
lime & shale	4497
lime & shale w/chert	4525
sandy lime	4595
lime w/shale strks	4618 RTD
Total Depth	

Mississippian	4291
Kinderhook	4323
Viola	4386
Simpson	4524
Arbuckle	4583

DST 4208-41', op 30 min, very weak blow
1", rec. 10' mud. IBHP 0#/20", FBHP 0#/20"
FP 0#-0#.

DST 4374-87', op 45 min. very weak blow
4 mins, rec. 15' mud., IBHP 1980#/20 mins.
FEHP 35#/20 mins. FP 40#-44#.

TOPS:
Heebner 3597
Base Oread 3630
Tonganoxie Sand 3737
Lansing 3759
Base Kansas City 4199
Massey 4220