

29-31-45W
14W

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


Company - DEEP ROCK OIL CORP.
Farm - Skinner "B" No. 5.

SEC. 29 T. 31 R. 14 W
SW NW NW

Total Depth. 4578'
Comm. 9-28-47
Shot or Treated.
Contractor.
Issued. 12-20-47

Comp. 11-6-47

County. Barber
KANSAS



Elevation. 1800 ft

CASING:
10 3/4" 291'
7" 4536'

Production. Pot. 2231 B.

Figures Indicate Bottom of Formations.

acidized with 3000 gals.

red bed	40
red bed sand	260
red bed	455
red bed shells	670
anhydrite	725
shale & shells	850
red bed	970
red bed & shale	1345
shale & shells	1450
salt & shale	1588
shale & shells	1980
shale & lime	2110
lime	2480
lime & shale	2670
shale & shells	2790
lime & shale	2875
shale & shells	3090
shale & lime	3140
shale & shells	3225
lime brkn	3315
shale	3235?
lime	3460
lime & shale	3520
shale	3585
lime & shale	3775
shale	3810
shale & shells	3980
K.C. lime	4015
lime	4320
cherty lime	4350
lime & shale	4572
Total Depth.	4572
chert lime	4578
lime brkn dolomite	4578

Douglas	3840
Iatan Ls (Brwn ls)	3940
Lansing	3965
Penn. Cong.	4517
Kinderhook Sh	4537
Viola Dolo (Maquok)	4567

Geological Tops:
Heebner shale 3785