

30-31-14W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - AMERADA PETROLEUM CORPORATION
Farm - G. B. Oldfather No. 2

SEC. 30 T. 31 R. 14W
NE NW SE
330' S. of N line 1650' E of
T. line of SE/4
County, Barber

Total Depth. 4621'

Comm. 8-8-47


Comp. 8-25-47

Shot or Treated.

Contractor. Glenn Peel

Issued. 11-14-47

KANSAS



CASING:

8-5/8" 309' Cem. W/250 Sx.

5-1/2" 4610' Cem. W/250 Sx.

Elevation. 1823 *at surface*

Figures Indicate Bottom of Formations.

Production. Pumped 49 Bbls. 0 in
14 hrs. - G.O. 4/10% BS &
2/10% water.

clay	35
shale and shells	360
sand & shale streaks	380
sand	410
shale & sand streaks	570
red bed	800
shale	860
anhydrite	895
shale & shells	925
shale & salt	947
salt & shale streaks	1132
shale & shells	1200
shale & anhydrite streaks	1430
shale & sand streaks	1650
shale & soft lime	1750
shale & lime	1940
bromide lime & shale	2055
lime broken	2170
lime	2470
lime & shale	2520
lime broken & shale	2605
lime & shale	2725
shale & lime	3420
lime & shale streaks	3490
lime & shale	3580
lime & shale streaks	3645
lime & shale	3705
shale & lime streaks	3740
lime broken & shale	3865
lime & shale	4185
lime	4245
lime & shale	4265
lime	4300
lime & chert	4330
lime & shale	4400
lime	4435
lime & shale	4603

TOPS:

Lansing	4018'
Conglomerate	4554'
Kinderhook	4574'
Viola	4610'

shale	3810
lime	4613
cherty dolomite	4621
lime	4621

Total Depth

No electric log made on this well

Rotary Tools 0' - 4613'

Cable Tools 4613' - 4621'