

Geological Report

American Warrior Inc.
Marsh #1-33
515' FSL & 405' FWL
Sec. 33 T31S R15W
Barber County, Kansas

James Dilts
Geologist

RECEIVED
JUN 08 2010
KCC WICHITA

American Warrior, Inc.

General Data

Well Data:

American Warrior Inc.
Marsh #1-33
NE-SW-SW-SW
515' FSL & 405' FWL
Sec. 33 T.31S R.15 W.
Barber County, Kansas
API # 15-007-23, 331-0000
Lat N 37 17' 53.220438
Long W 98 57' 57.443956

Drilling Contractor: Duke Drilling Co.

Spud Date: 8/5/2008

Rotary TD Date: 8/14/2008

Rotary TD: 4984'

Elevation: 1989' Ground Level
2002' Kelly Bushing

Casing: Surface 235' 8 5/8" 23# surface casing set at
230' w/ 225 sx 60/40 w/3%cc 2%gel
Production 4964' 5.5" 15.5# at 4979' w/165 sx
AA2

Samples: 10' wet and dry, 3500' to RTD

Drilling Time: 3500' to RTD

Electric Logs: DIL/CDL//BHCS/CNL

Drillstem Tests: One

Problems: None

RECEIVED
JUN 08 2010
KCC WICHITA

Formation Tops

Marsh 1-33

| | |
|-------------|------------|
| Heebner | 4124'-2153 |
| Toronto | 4136'-2165 |
| Brown Lime | 4273'-2302 |
| Lansing | 4295'-2324 |
| BKC | 4686'-2677 |
| Marmaton | 4697'-2726 |
| Pawnee | 4782'-2811 |
| Ft Scott | 4812'-2841 |
| Cherokee | 4824'-2853 |
| Mississippi | 4832'-2861 |

DST 1: Mississippi

Interval: (4820'-4782') Anchor Length 38'

I.F. Strong Blow BOB Imm IF 85-231#

I.S.I No Blow ISI 1305#

F.F Strong Blow BOB Imm FF 81-90#

F.S.I Weak to Fair Blow FSI 1303#

Recovery: 4494' GIP

186' GM

%gas %oil %w 100%m

Summary: Due to structural position and log information, the decision was made to case the Marsh #1-33 for further evaluation.

Suggested perforations: Mississippi 4790'-4800'

Lansing 4254'-4258' prior to abandonment

Lansing 4482'-4486' prior to abandonment

Respectfully Submitted,
James F Dilts

RECEIVED
JUN 08 2011
KCC WICHITA