

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- AYLWARD
Farm- Skinner "A"


No. 1

SEC. 33 T. 31 R. 15W
CSE

Total Depth. 4763
Comm. 12-11-52
Shot or Treated.
Contractor.
Issued. 2-28-53

Comp. 2-4-53

County Barber
KANSAS



CASING:

8 5/8" 295' cem. w/250 sx
5 1/2" 4741' cem. w/200 sx

Elevation. 1918 DF
1928 (21)
Production. 4,000,000 Gas

Figures indicate Bottom of Formations.

drillers log 133-	3700	sand	4128	limestone, brown ,	
no log	133	shale brown , sand strks		chert	4669
red beds & shale	485	gry-brown lime	4177	shale, brown shale	4678
red beds	500	limestone, brown	4180	sand, sdy shale	4686
red beds & shale	800	shale, limestone	4188	limestone brown,	
shale & limestone	1034	limestone	4194	chert	4698
anhydrite	1080	shale, limestone	4203	shale green-gry	4702
no log	1274	limestone brown	4218	limestone, brown	
limestone & shale	1485	limestone	4226	chert	4709
shale & shells	1625	limestone, shale	4234	limestone,	4715
shale	1700	limestone brown	4250	shale green & brn	4719
shale & shells	1895	limestone, chert	4264	limestone	4725
limestone	2555	limestone	4278	sand brown, chert	
limestone & shale	2570	limestone	4285	red, gry-green,	
shale	2610	lime stone, chert		shale green	4741
limestone	2755	brown	4304	chert brown,	4760
limestone broken	2785	shale	4308	limestone, green-brn	
limestone & shale	3000	limestone,	4320	shale gry-green	4763
limestone broken	3135	limestone	4340	Total Depth	
shale & limestone	3200	limestone, chert			
sandy limestone &		brown	4363	Tops:	
shale	3375	shale	4366	Stone Corral	1034
limestone broken	3495	limestone, chert	4374	Ft. Riley ?	2510
shale	3585	limestone, chert	4392	Douglas	4050
shale & limestone	3615	limestone, chert	4400	Douglas Sand	4072
limestone broken	3700	shale	4405	Base Douglas	4177
limestone, chert	3704	limestone	4411	Brown Lansing	4177
limestone, sandgrains		limestone	4414	Lansing	4203
& chert	3749	limestone, chert gry-		Base-Kansas City	4580
limestone, brown		brown	4426	Marmaton	4580
porosity	3772	limestone	4431	Conglomerate	4725
limestone, chert	3788	limestone, chert gry		Miss.	4741
limestone brown, poro.		and brown	4446		
shale	3808	shale gry-green	4451	DST: 4723-63' open 10	
limestone brown	3830	limestone	4462	min. gas to surface in	
limestone, shale		limestone, brown, chert		1 min. rec. 85' gas cut	
green	3872		4489	mud BHP 1600#.	
limestone	3910	limestone, shale	4506	No show 3704-3749'	
limestone	3919	limestone, chert	4512	No show 3749-3772'	
limestone, shale	3929	limestone, chert	4536	No show 3788-3808'	
limestone	3954	limestone brown, chert		No show 3910-3919'	
limestone brown	3965	brown , shale	4552	No show 3929-3954'	
limestone brown strks		limestone, chert	4570	Possible light oil stain?	
Heebner-like blk		limestone	4580	3954-3965'	
shale	3995	shale green & maroon	4586	No show 3965-3995'	
limestone	3998	limestone, brown, red		Most of sand barren. Some	
shale blk Heebner	4006	weathered, chert brown		pieces with fair stain	
Limestone Leavenworth		some shale strks	4608	4095-4111'	
	4012	limestone, chert		Mostly barren, some pieces	
shale Snyderville	4034	brown.	4621	stained 4113-4128'	
limestone chalky		shale green	4628	No show 4218-4226'	
Toronto	4050	limestone, chert	4633	No show 4234-4250'	
shale green mica	4072	shale green	4637	No show 4278-4285'	
sand	4095	limestone, brown &		No show 4308-4320'	
sand brown	4111	red , chert	4653	Possible tr. sli. stain	
limestone brown	4113	limestone, shale	4658	4374-4392'	

OVER

Cont'd.

Company- Aylward

Farm - No. 1 Skinner "A"

33-31-15W

CSE

No show 4411-4414'

No show 4451-4462'

No show 4506-4512'

Fair stain, no odor

4678-4686'

Fair odor and stain, some
gas bubbles and show free

oil 4741-4760'

Note: All measurements are
from the top of the rotary
bushing.