

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


33-31-15W

Company- AYLWARD DRILLING CO.
Farm- Skinner "A" No. 2

SEC. 33 T. 31 R. 15W
NW SE NW

Total Depth. 4718'
Comm. 2-21-56 Comp. 3-12-56
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 6-2-56

County Barber
KANSAS



Elevation. 1894' DF

Production. 42 BOPD

Figures indicate Bottom of Formations.

red rock	106
red rock and sand	395
Dakota sand	494
red rock and gyp	815
anhydrite	830
shale and shells	1140
gray shale with lime streaks	1400
lime and shale	1790
lime	1855
lime and shale	2015
lime	2050
lime and shale	2325
lime	2405
lime and shale	2460
lime	2475
lime, broken	2530
lime and shale	3105
lime	3130
shale and lime	3285
broken lime	3360
sandy lime	3485
lime and shale	3563
sandy lime	3592
lime	3880
sandy lime	3973
lime and shale	4059
lime	4101
sandy lime	4145
lime and shale	4195
lime	4610
lime and shale	4665
lime	4700
lime and chert	4704
lime	4718
Total Depth	

Tops:	
Heebner	3990
Base Oread	4026
Douglas Sand	4067
Brown Lime	4140
Loring	4644
Conglomerate	4698
Mississippi	4702

Cable Tool Data:
Drilled plug and drilled deeper to 4714;
water 4714-18; plug back to 4711; sandfrac;
perf. 20 holes 4686-4701; fracture treatment;
recover load; test 42 BOPD; POP

