

4-31-15W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas




Company- AYLWARD DRILLING & LEHEN DRIG., INC.
Farm- Lenkner No. 1

SEC. 4 T. 31 R. 15W
C NW SW

Total Depth. 4851'
Comm. 1-11-62 Comp. 1-29-62
Shut or Treated.
Contractor. Aylward Drig.
Issued. 6-16-62

County Barber
KANSAS



Elevation. 1776' KB

CASING:
8 5/8" 795' cem w/765 sx.

Production. Dry

Figures Indicate Bottom of Formations.

red bed, gyp & shells	40
red rock	70
sand	85
red rock	170
shells	197
red rock & gyp	380
red bed	795
red bed, shale & shells	1115
shale & shells	1310
shale - lime streaks	1500
shale & shells	1700
lime & shale streaks	1890
lime & shale	2050
lime	2675
broken lime & shale	2795
lime	2940
broken lime & shale	3135
lime & shale	3394
lime	3900
lime & shale	3980
lime	4174
lime & shale	4215
lime	4420
sand & lime	4480
lime	4568
lime & chert	4610
chert	4678
lime & chert	4701
chert & shale	4725
sandy shale	4780
shale	4820
lime	4851
Total Depth	

Lansing-Kansas City	3936
Massy Zone	4372
Viola	4530
Simpson	4704
Simpson Sand	4742
Arbuckle	4794

DST 4345-85', op 40 min., Rec. 50' mud.
IBHP 162#/30 min, FBHP 92.8#/50 min,
FP 31#-42#.

Tops and drill stem test are taken from Schlumberger measurements, which are 25' higher than drillers measurements.

TOPS: (LOG)	
Heebner	3755
Douglas	3798
Brown Limestone	3906

