

15-007-20670

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOG

S. 24 T. 31S R. 15W E
W
Loc. 2510' FSL & 330' FEL
County Barber

API No. 15 — 007 — 20,670
County Number

Operator
Texas Oil & Gas Corp.

Address
200 W. Douglas, Suite 300, Wichita, Kansas 67202


Well No. 1 Lease Name Hull "B"

Footage Location
2510 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor H-30 Drlg., Inc. Geologist High Plains Consulting, Ltd.

Spud Date 9-19-78 Total Depth 4875' P.B.T.D. 4834'

Date Completed 11-07-78 Oil Purchaser N/A



Elev.: Gr. 1821'
DF 1826' KB 1829'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	24#	308'	Lite-weight Common	100 150	2% Gel, 3% CaCl
Production		2-7/8"	6.5#	4874'		250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD			2	Deep Penet.	4633-35'
			2		"
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
559 gal. acid	4633-35 & 4625-27'

INITIAL PRODUCTION

Date of first production Shut-in	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil N/A bbls. Gas + 1200 MCF Water N/A bbls. Gas-oil ratio N/A CFPB
Disposition of gas (vented, used on lease or sold) Shut-in	Producing interval(s) 4633-35' & 4625-27' (Mississippi)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Texas Oil & Gas Corp.

Well No.

Lease Name

1

Hull "B"

Shut-in Gas Well

S 24 T 31S R 15W E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herrington	2168	-339		
Cottonwood	2688	-859		
Heebner	3881	-2052		
Douglas Sd	3915	-2086		
Lansing	4033	-2204		
Pawnee	4513	-2684		
Ft. Scott	4552	-2723		
Mississippi	4622	-2793		
Kinderhook	4806	-2977		
Chattanooga	4826	-2997		
Viola	4837	-3008		
TD	4875	-3046		
PBTD	4834	-3005		
DST #1, 3688-3720', (Lecompton) w/results as follows:				
IFP/30": 53-42#, weak blow decr to slight				
ISIP/60": 1453#				
FFP/15": 106-85#, weak blow decr to slight				
FSIP/30": 1422#				
Rec 186' SW & SMCW.				
DST #2, 4585-4655', (Mississippi) w/results as follows:				
IFP/30": 256-962#, GTS/3", gauged 3752 MCFD incr to 4946 MCFD				
ISIP/45": 1699#				
FFP/45": 795-868#, strong blow, gauged 4349 MCFD & stabilized				
FSIP/90": 2165#				
Rec 372' GW.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Harold A. Brown

HAROLD A. BROWN

Signature

District Geologist

Title

November 29, 1978

Date

COMPANY Texas Oil & Gas Corporation

SEC. 24 T. 318 N. 15W
LOC. 2510' FSL & 330' FEL

FARM Hull "B"

NO. 1

COUNTY Barber

ROTARY TOTAL DEPTH 4,875'

COMM. September 19, 1978

COMP. September 30, 1978

CONTRACTOR H-30, Inc.

ISSUED October 9, 1978

CASING

10 3/4"

8 5/8" Set at 308' cemented w/250 sxs cement

ELEVATION 1,817' K.B.

5 1/2"

4 1/2"

2 7/8" Set at 4,874' cemented w/250 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale

800'

Shale and Lime

2,010'

Lime and Shale

2,186'

Shale and Lime

2,945'

Lime and Shale

3,720'

Shale and Lime

3,945'

Lime and Shale

4,875'

Rotary Total Depth

4,875'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 9th day of