

IMPORTANT
Kans. Geo. Survey request
samples on this well.

KANSAS DRILLERS LOG

API No. 15 — 007 — 20,701
County Number

Operator

Texas Oil & Gas Corp.

Address

Suite 300, 200 West Douglas Wichita, Kansas 67202

Well No. #1

Lease Name
Hull "C"

Footage Location

455 feet from (N) (S) line 840 feet from (E) (W) line

Principal Contractor

Slawson Drlg., Inc.

Geologist

Charley V. Shank

Spud Date

12-21-78

Total Depth

5130'

P.B.T.D.

N/A

Date Completed

1-04-79

Oil Purchaser


N/A

S. 25 T. 31 R. 15 E
W

Loc. 455' FNL & 840' FEL NE

County Barber

640 Acres
N



Locate well correctly

Elev.: Gr. 1853'

DF KB 1858'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"	28#	311'	Common	250	2% Gel, 3% CaCl

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
N/A	N/A	N/A

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A

TUBING RECORD

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
N/A		N/A			
Rate of production per 24 hours	Oil	Gas	Water	Gas-oil ratio	
	N/A bbls.	N/A MCF	N/A bbls.	N/A	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
N/A			N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Texas Oil & Gas Corp.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Hull "C"	Dry Hole	
S <u>25</u> T <u>31S</u> R <u>15W</u> ~~X~~ W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Herrington	2208	-350	
Cottonwood	2723	-865	
Howard	3423	-1565	
Heebner	3920	-2062	
Top Douglas Group	3956	-2098	
Douglas ss	3968	-2110	
Lansing	4094	-2236	
Pawnee	4536	-2678	
Ft. Scott	4576	-2718	
Mississippi	4648	-2790	
Kinderhook	4689	-2831	
Chattanooga	4709	-2851	
Viola	4720	-2862	
Simpson	4833	-2975	
Simpson sh	4890	-3032	
Arbuckle	4942	-3084	
TD	5130	-3272	
DST #1, 4147-78' (Lansing) w/results as follows: IFP/30": 102-174#, fair blow ISIP/60": 1477# FFP/45": 221-266#, fair blow FSIP/90": 1487# Rec 120' Gas in pipe, 160' O&GCM, 360' O&GCSW.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	HAROLD A. BROWN Signature District Geologist Title January 10, 1979 Date		