

34 - 31 - 15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO. ET AL
Farm- Skinner "D" No. 2

SEC. 34 T. 31 R. 15W
SW NE SE

Total Depth. 5037'
Comm. 8-28-57 Comp. 9-14-57
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 12-7-57

County Barber
KANSAS



Elevation. 1914' RB

Production. 16,250,000 CFG

CASING:

8 5/8" 211' cem w/160 sx.
5 1/2" 4810' cem w/100 sx.

Figures indicate Bottom of Formations.

red rock & gyp	400
sand	450
red bed & shells	955
red bed	1018
red bed & shells	1115
Anhydrite	1160
shale & shells	1365
salt	1425
shale & shells	1907
lime & shale	2180
lime	2260
lime & shale	2700
shale & lime	2905
lime & shale	3075
shale & lime	3720
lime & shale	3928
shale	4001
shale & lime	4029
sand & sandy shale	4083
sandy shale & lime	4172
lime	4571
lime & shale	4665
lime	4699
chert	4730
lime & shale	4918
cherty lime	5037 RTD
Total Depth	

TOPS:

Heebner Shale	3968
Base Oread	4011
Douglas Sand	4029
Lansing	4150
Base Kansas City	4573
Mississippian	4670
Kinderhook Shale	4760
Viola	4891
Simpson	5014

DST 4672-4730, open 1 hr. Gas to surface
in 2 1/2 min., gauged 1,450 MCFG/50 min.
dec. to 1,140 MCFG/1 hr. Rec. 150' GCM
FP 330#-230#. IBHP 1630#/25 min. -
FBHP 1190#/20 min.