


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

35-31-15W

Company- NATIONAL COOPERATIVE REFY. ASS'N. & SEC. 35 T. 31 R. 15W
Farm- Skinner "B" No. 1 AylWARD DRIG. CO. SE SE SW

Total Depth. 5145'
Comm. 5-4-57 Comp. 5-28-57
Shot or Treated.
Contractor. Aylward Drig. Co.
Issued. 8-23-58

County Barber
KANSAS



CASING:
8 5/8" 211' cem w/150 sx.

Elevation. 1905' DF

Production. Dry

Figures indicate Bottom of Formations.

red rock & gyp	100	DST 4357-70, op 1 hr, fair bl. thruout, rec.
shells & red rock	800	50' sl. O&GCM, IBHP 1345#/20 min. FBHP 245#/ 20 min. FP 0-0#.
red rock	1036	
shale w/lime streaks	1535	
shale & shells	1925	DST 4675-4757 Mis-run.
shale & lime	2100	
lime & shale streaks	2235	DST 4687-4757, op 1 hr, very tight blow, rec.
lime	2805	10' mud, FP 55-55#, BHP 55#/20 min.
lime & shale	2960	
shale & lime	3095	
lime & shale	3820	
shale & lime	3951	
lime & shale	4033	
shale & lime	4065	
lime & shale	4159	
lime	4190	
lime & shale	4206	
lime	4810	
lime & shale	4870	
shale & lime	4885	
lime	4922	
cherty lime	4930	
lime	5000	
sandy lime & shale	5026	
sand	5034	
lime & shale	5075	
shale & lime	5113	
lime	5145 RTD	
Total Depth		

TOPS:
Anhydrite (scout) 1975
Heebner 3958
Leavenworth 3982
Toronty 3991
Douglas 4010
Douglas Sand 4054
Brown Lime 4114
Lansing 4135
Base Kansas City 4538
Massey 4609
Kinderhook 4679
Viola 4864
Simpson Sand 4988
Simpson Shale 5066
Arbuckle 5119

DST 4037-65, op 1 hr, fair steady blow
thruout, rec. 240' wtry, mud, 270' SW.
IBHP 1500#/20 min, FBHP 1395#/20 min.
FP 140-300#/20 min.

DST 4164-84 op 1 hr, fair bl. 22 min.,
died, rec. 30' sl. Oil specked mud.
IBHP 128#/20 min, FBHP 113#/20 min.
FP 33-44#/20 min.

DST 4196-4206, op 1 hr, gas to surf. in
13 min, not strong enough to gauge. rec.
60' sl. O&GCM, IBHP 1618#/20 min, FBHP 731#/
20 min. FP 34-38#.