


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATIONAL COOPERATIVE REFG. ASS'N.
Farm- Skinner "B" No. 2

SEC. 35 T. 31 R. 15W
SE SE SW

Total Depth. 4780'
Comm. 6-3-57. Comp. 6-19-57
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 10-18-58

County Barber
KANSAS



Elevation. 1913' KB

Production. 18,000,000 CFG

CASING:

8 5/8" 231' w/175 sx cem.
5 1/2" 4779' w/250 sx cem.

Figures indicate Bottom of Formations.

shale, red rock	60
gyp	95
shale, red bed	280
red rock, shale	1100
red bed, red rock	1410
salt	1470
shale, lime shelves	1765
shale, lime	2200
lime, shale	2517
lime, some shale	2555
lime	2695
lime w/shale	2785
lime, shale	3255
shale, some lime	3365
shale	3395
lime, shale	3640
sand,	3680
sand, shale	3731
shale w/lime	3772
lime, shale	4011
lime, shale, sand	4102
sand	4125
lime, shale	4238
lime	4336
lime, some shale	4413
lime	4722
chert, lime	4747
chert, shale	4752
lime, shale	4780
Total Depth	

TOPS:	
Heebner	3980
Toronto	3996
Douglas	4005
Lansing	4157
B/Kansas City	4588
Mississippian	4678
Kinderhook	4730

BST #1 - 4221-30 Open 1 hr.,
Rec. 300' gas in drill pipe,
32' Hvly OCM. IBHP 1240#/20"
FBHP 20#/20". FPG//20#.

DST #2 - 4693-4720 Open 1 hr.
Gas to surf. in 2", gauged
2,930 MCFG/5", 3,690/9",
4,070/15", 3,970/30", 3,970/45"
3,970 MCFG/60". Rec. 25' SI,
GCM. IEHP 1640#/20", FBHP 1620/
20", FP 745-745#.

DST #3 - 4720-47 Open 1 hr. Gas
to surf. 2" 3,690 MCFG/5", 4,640
15", 5,210/30", 5,210/45", 5,210/
60". Red. 45' SI. GCM. IEHP Not
obtained, FBHP 1634#/20". FP
1240-1340#.