

35 - 31 - 15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATIONAL COOPERATIVE REFINERY ASS'N.
Farm- Skinner "H" No. 1

SEC. 35 T. 31 R. 15W
CS/2 NW NW

Total Depth. 4710'
Comm. 9-23-57 Comp. 10-9-57
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 12-7-57

County Barber
KANSAS



CASING:
8 5/8' 232' cem w/195 sx.

Elevation. 1908' KB

Production. Dry

Figures indicate Bottom of Formations.

gyp rock & red rock	70
red bed, gyp & sand	231
red bed, shale & shells	615
red rock & shale	1260
Anhydrite	1495
shale & lime streaks	1925
shale & lime	1945
lime	2330
lime & shale	2400
lime	2560
lime & shale	2765
lime	2970
lime & shale	3316
lime, shale & sand	3485
lime & shale	3625
sand	3670
lime & shale	4163
lime	4588
lime & shale	4627
lime	4661
chert	4680
lime & shale	4702
lime, chert & shale	4710 RTD
Total Depth	

TOPS:

Heebner	3960
Leavenworth	3966
Toronto	3978
Douglas	3993
1st Douglas Sand	4015
2nd Douglas Sand	4051
Lansing	4120
Base Kansas City	4526
Massey	4593
Mississippian	4658
Kinderhook	4687

DST 4680-4710, open 1 hr., Rec. 12' mud,
IBHP 150# - FBHP 20#, FP 20#-20#.

DST 4659-80, open 1 hr., Gas to surface
in 30 min. Rec. 20' mud. IBHP 1280#,
FBHP 665#. FP 20#-20#