

Oil Producers Inc. of Kansas
Robbins #1 SWD in Comanche Co., KS
Rework Report

7/09/02 -

COMANCHE ON LOCATION TO DRILL OUT CASING TO 4639' (TUBING TALLY).
CIRCULATE 1 HR.

ROOH - w/ WORKING STRING AND BIT

SIoux TRUCKING ON LOCATION TO DELIVER 2 3/8" DUO LINE TUBING AND WELLHEAD
SET-UP.

ELI WIRELINE ON LOCATION TO RUN CORRELATION LOG AND SONIC CEMENT BOND LOG.

FOUND TTL DEPTH - 4462'

FOUND TOP OF CEMENT - 4450'

ELI WIRELINE ON LOCATION TO PERFORATE PROPOSED INTERVALS IN LANSING,
UTILIZING 32-GRAM EXPENDABLE CASING GUNS.

PERFORATE LANSING AS FOLLOWS:

LANSING	4512' - 4515'	4/FT
LANSING	4542' - 4548'	4/FT
LANSING	4564' - 4570'	4/FT

COMANCHE SWABBED WELL DOWN TO 2500'.
SHUT DOWN FOR NIGHT.

7/10/02 -

COMANCHE ON LOCATION TO SWAB WELL DOWN TO TTL DEPTH.

GREAT PLAINS FLUID SERVICES ON LOCATION w/ 130 BBL MISSISSIPPI WATER.

ACID SERVICES ON LOCATION TO ACIDIZE LANSING PERFS w/ 2500 GAL MCA 15% w/ 100
BALL SEALERS.

ACIDIZE LANSING PERFORATIONS AS FOLLOWS :

PUMP 500 GAL MCA 15% ACID

PUMP 2000 GAL MCA 15% ACID w/ 100 BALL SEALERS EQUALLY SPACED

PRESSURE TO 900#, BREAK BACK SLOW

DISPLACE 500 GAL ACID @ 5 BPM - 800#

DISPLACE 2000 GAL ACID @ 5 BPM - 850#

NOTE: GOOD BALL ACTION. PEAKS @ 1200#

ISIP - 275#

TTL LIQUID LOAD - 135 BBL

COMANCHE TO RIH w/ JAR SWAB TO KNOCK OFF ANY BALL SEALERS REMAINING ON
PERFS.

7/10/02 CONTINUED -

GREAT PLAINS FLUID SERVICE ON LOCATION TO GRAVITY FEED MISSISSIPPI WATER INTO WELL.

NOTE : WELL DID NOT TAKE WATER ON VAC. TOOK WATER ON 25# PRESSURE (SLIGHT). DECISION MADE TO RE-ACID WELL.

COMANCHE SWAB DOWN WELL TO TTL DEPTH.

ACID SERVICES ON LOCATION TO ACIDIZE LANSING PERFS w/ 2000 GALS REG 28% ACID.

ACIDIZE LANSING PERFS AS FOLLOWS:

PUMP 2000 GAL REGULAR 28% HCL ACID
PRESSURE TO 200#
DISPLACE 2000 GAL ACID @ 2 BPM - 200#
ISIP - 150# (15 MIN. 50#)
TTL LIQUID LOAD - 122 BBL

GREAT PLAINS ON LOCATION TO GRAVITY FEED WELL.
FOUND WELL TOOK TO VAC @ .182 BPM = 10.92 BPH.

COMANCHE RIGGED TO SWAB DOWN LANSING PERFS.
FOUND FLUID LEVEL @ 50'.
RECOVERED 120 BBL. DID NOT GET WELL SWABBED DOWN.
SHUT DOWN FOR NIGHT.

7/11/02 -

COMANCHE ON LOCATION TO CONTINUE SWAB DOWN.
FOUND FLUID LEVEL @ 1700'.
SWAB WELL DOWN TO TTL DEPTH.
COMANCHE RIGGED TO SWAB TEST LANSING PERFS.

SWAB TEST AFTER ACID AS FOLLOWS:

½ HR SWAB - REC. 8.67 BBL

FLUID LEVEL - 4100'

DECISION MADE TO RIH w/ PACKER AND SEAL TITE TUBING.
WRONG PACKER SENT.
SHUT DOWN FOR NIGHT.

7/12/02 -

COMANCHE ON LOCATION TO RIH w/ PACKER AND SEAL TITE 2 3/8" TUBING.

RUN SEAL TITE TUBING (2 3/8") AS FOLLOWS:

CHANGE OVER & RUBBER OF PACKER CENTER	1.35'
135 JTS 2 3/8" SEAL TITE TUBING	4443.35'
K.B. (5' < 2' ABOVE G.L.)	<u>3.00'</u>
TUBING SET @	4447.70'

NOTE: TUBING IS SET 64.3' ABOVE LANSING PERFS.

7/12/02 CONTINUED -

GREAT PLAINS FLUID SERVICE ON LOCATION TO MIT WELL w/ PACKER FLUID.

7/16/02 -

KCC REPRESENTATIVE WITNESSED MIT @ 300#.
MIT PASSED.

7/17/02 -

GABEL LEASE SERVICE ON LOCATION. LAYED APPROX. 4000' 2" POLY LINE ON TOP GROUND FROM #2 ROBBINS TO #1 ROBBINS SWD. MOVED 10' x 12' 200 BBL FIBERGLASS WATER TANK FROM #2 WELL TO #1 WELL SITE & TIED IN. WILL START PRODUCING WATER INTO SWD AS SOON AS KCC APPROVAL IS RECEIVED.

END OF REPORT
BRAD SIROKY