

1-31-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BARBARA OIL CO.
Farm. Robbins-Gallup "B" No. 1

SEC. 1 T. 31 R. 16W
C SW/4

Total Depth. 4720'
Comm. 10-10-58 Comp. 10-28-58
Shot or Treated.
Contractor. Pickrell Drlg.
Issued. 12-20-58

County Comanche
KANSAS



Elevation. 1899' RB

Production. 25,000,000 CFG

CASING:

8 5/8" 290' cem w/165 sx.
5 1/2" 4720' cem w/150 sx.

Meas. from top of RB

Figures Indicate Bottom of Formations.

top soil	10
red beds	290
red rock	315
shale & shells	1210
shale, shells & lime	1755
shale & lime	2025
lime	2600
lime & shale	2700
lime	2775
shale	2970
lime & shale	3012
shale	3170
shale & lime	3330
lime	4010
shale	4102
lime	4630
Mississippi	4683
lime	4715
Mississippi	4720 RTD
Total Depth	

TOPS:	SAMPLE	LOG
Heebner	3898	3898
Toronto	3912	3911
Douglas	3934	3932
Brown Lime	4079	4078
Lansing	4096	4095
Base Kansas City	4499	4498
Marmaton	4547	4548
Cherokee	4606	4604
Mississippi	4630	4630