

2-31-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- PICKRELL DRILG. CO. & BARBARA OIL CO.
Farm- Robbins-Gallup No. 1
"A"

SEC. 2 T. 31 R. 16W
C S/2 NW

Total Depth. 4895'
Comm. 8-6-58 Comp. 8-24-58
Shot or Treated.
Contractor. Pickrell Drilg. Co.
Issued. 5-23-59

County Comanche
KANSAS



Elevation. 1994.1

Production. 13,000,000 Gas.

CASING:

8 5/8" 312' w/175 sx cem.
5 1/2" 4894' w/150 sx cem.

Figures indicate Bottom of Formations.

sand	30
shale, sand	150
red beds	312
red shale	890
red rock, shale	940
salt, shale	1470
shale, shells	2115
lime, shale	2370
lime	2760
lime, shale	2975
shale	3245
shale, lime	3310
lime	3455
lime, shale	3640
lime	3784
lime, shale	3854
lime	3990
lime, shale	4086
lime	4592
lime, shale	4628
lime	4779
Mississippi	4810
lime	4895
Total Depth	

TOPS: SCOUT	
Hebner	4088
Toronto	4170
Lansing	4182
Mississippi	4780

S.L.M. @ 2000 - O.K.
3000 - O.K.
4000 - O.K.